

HAWKE'S BAY WATERWAY GUIDELINES

⊕ EROSION & SEDIMENT CONTROL



SAFEGUARDING YOUR ENVIRONMENT KAITIAKI TUKU IHO



Hawke's Bay Waterway Guidelines

Erosion and Sediment Control

Prepared by:
Earl Shaver, Aqua Terra International Ltd

Reviewed by:
Gary Clode, Manager - Engineering

Acknowledgement

This document for the Hawke's Bay Region is based on the Auckland Regional Council's Technical Publication No. 90 "Erosion and Sediment Control Guidelines for Land Disturbing Activities". The ARC gave permission to use their document and that permission is greatly appreciated.

Modifications to the ARC document have been made so there will be some differences to the ARC approach to account for advances in practice design and to reflect local conditions.

Note

This document is a living document and may be reviewed from time to time as industry standards change and best practice evolves. Please contact Hawke's Bay Regional Council to ensure the latest version is used.

April 2009
ISBN NO 1-877405-35-3
HBRC Plan Number 4109

© Copyright: Hawke's Bay Regional Council

Contents

1	Overview of the guidelines	1
1.1	Intent of These Guidelines	1
1.2	How These Guidelines Work.....	1
1.3	Erosion and Sediment Control in the Hawke's Bay Region	2
1.4	Current Legislation: When is a Resource Consent Required?	3
1.5	When is Erosion and Sediment Control Required?.....	3
1.6	Hawke's Bay Soils: The Prime Importance of Erosion Control.....	4
2	Basic erosion facts	6
2.1	Types of Erosion	6
2.2	Factors Influencing the Erosion Process	9
3	Principles to Follow	11
3.1	Minimise Disturbance.....	11
3.2	Stage Construction.....	11
3.3	Protect Steep Slopes	11
3.4	Protect Watercourses.....	11
3.5	Stabilise Exposed Areas Rapidly.....	12
3.6	Install Perimeter Controls	12
3.7	Employ Detention Devices	12
3.8	Get Educated.....	12
3.9	Make Sure the Plan Evolves	12
3.10	Assess and Adjust.....	13
4	Types of Land Disturbing Activities.....	14
4.1	Trenching.....	14
4.2	Works Within a Watercourse.....	14
4.3	Cleanfills	15
4.4	Small Sites and Permitted Activities	15
4.5	Earthworks.....	16
4.6	Roading	16
4.7	Quarries and Vegetation Removal	17
5	Erosion Control Practices.....	18
5.1	Runoff diversion channel.....	19
5.2	Contour drain	22
5.3	Benched slope	24
5.4	Rock check dams.....	26
5.5	Top soil placement.....	29
5.6	Revegetation.....	31
5.7	Hydroseed.....	34
5.8	Mulching	36
5.9	Turfing.....	39
5.10	Erosion control matting	41
5.11	Stabilised construction entrance.....	45
5.12	Pipe or Flume drop structure	47
5.13	Level spreader	50
5.14	Surface roughening.....	53
6	Sediment Control Practices.....	55
6.1	Sediment Retention Pond	56
6.2	Flocculation.....	67
	Comments.....	71
6.3	Silt Fence.....	74
6.4	Super silt fence	77
6.5	Straw Bale Barrier.....	80
6.6	Stormwater Inlet Protection	82
6.7	Decanting earth bund.....	85

6.8	Decanting topsoil bund.....	88
6.9	Sump/sediment pit	89
7	Quarries	91
7.1	Road Access.....	91
7.2	Stormwater.....	91
7.3	Overburden Disposal	92
7.4	Stockpile Areas	92
7.5	Rehabilitation of Worked Out Areas	92
7.6	Riparian Protection Areas	93
7.7	Maintenance Schedule for Erosion and Sediment Control or Treatment	
	Structures	93
	Appendix A.....	94