



# Ohiti Road (Omāhu) Flood Protection Stopbank Works

## Summary of Design for Resource Consent Purposes

**Prepared for**

Hawke's Bay Regional Council

**Prepared by**

Tonkin & Taylor Ltd

**Date**

September 2025

**Job Number**

1017353.2402



**Together we create and sustain a better world**

[www.tonkintaylor.co.nz](http://www.tonkintaylor.co.nz)

## Document Control

Title: Ohiti Road (Omāhu) Flood Protection Stopbank Works					
Date	Version	Description	Prepared by:	Reviewed by:	Authorised by:
3 September 2025	1	Summary of Design for Resource Consent Purposes	R. King	J. Yule	T. Morris

### Distribution:

Hawke's Bay Regional Council

1 PDF copy

Tonkin & Taylor Ltd (FILE)

1 PDF copy

## Table of Contents

<b>1</b>	<b>Introduction</b>	<b>1</b>
1.1	Project aim and objective	1
<b>2</b>	<b>Site location and description</b>	<b>3</b>
2.1	Site history and background	4
<b>3</b>	<b>Design inputs and assumptions</b>	<b>5</b>
3.1	Survey data	5
3.2	Hydrology	5
3.3	Existing infrastructure	5
3.4	Scope of work	6
3.5	Consent framework	7
<b>4</b>	<b>Stopbank preliminary design</b>	<b>7</b>
4.1	Flood model	8
4.2	Design functional requirements summary	9
<b>5</b>	<b>Transport</b>	<b>9</b>
<b>6</b>	<b>Geotechnical</b>	<b>10</b>
6.1	Borrow materials	10
6.2	Geotechnical considerations for construction	11
<b>7</b>	<b>Culverts, swales and stormwater management</b>	<b>11</b>
<b>8</b>	<b>Erosion and sediment controls</b>	<b>12</b>
<b>9</b>	<b>Consenting</b>	<b>13</b>
<b>10</b>	<b>Conclusions</b>	<b>13</b>
<b>11</b>	<b>Applicability</b>	<b>14</b>
	<b>Appendix A Preliminary Design Drawings</b>	
	<b>Appendix B Consent conditions</b>	
	<b>Appendix C Risk Register</b>	

## Executive Summary

This report is to be used for resource consent application only.

This report outlines the preliminary design details for the proposed Ohiti Road (Omāhu) Flood Protection Stopbank Works. This project aims to reduce flood risks to the Ohiti and Omāhu settlements by constructing new stopbanks to provide additional protection from flows from the Okawa Stream and Ngaruroro River.

The stopbank design has been based on flood modelling developed by T+T for HBRC for the Okawa stream catchment. The stopbank is designed to contain a 100-year ARI event considering a RCP8.5 2050 climate change scenario for the Okawa Stream and present day 100-year ARI flood level for the Ngaruroro River. A freeboard of 700 mm has been considered above these levels to inform the stopbank crest levels, with localised exceptions and no allowance for long term settlement of the embankment.

Stopbanks have generally been designed with a 1V:2.5H batter, with the exception of the western section of the Chesterhope Upper stopbank which incorporates a steeper 1V:1.8H batter to fit within the existing easement. Stopbanks are to be constructed from material extracted from the nearby borrow site.

In order to accommodate the stopbanks both Ohiti Road and Taihape Road need to be raised locally to accommodate the stopbanks passing below. Some property accessways also need to be raised and realigned to accommodate the proposed works.

New stormwater infrastructure inclusive of new culverts and swales have been incorporated into the design to ensure adequate drainage exists around the dwellings and accessways.

## 1 Introduction

Tonkin & Taylor Ltd (T+T) was engaged by Hawke’s Bay Regional Council (HBRC) to undertake design of the proposed Ohiti Road (Omāhu) Flood Protection Stopbank Works. This work has been carried out in accordance with the terms and conditions within our letter of engagement dated 27 June 2023<sup>1</sup> and variation order (VO3) dated 19 September 2024<sup>2</sup>.

This report is to be used for resource application only. All other users should refer to the previously issued preliminary design report<sup>3</sup>, which includes further considerations for constructors. The aim of this report is to summarise the preliminary design aspects of new stopbanks, stormwater infrastructure including new swales and culverts, roading realignment and associated infrastructure, and borrow site at Omāhu, Hastings, Hawkes Bay. Further work is required to develop designs suitable for contractor procurement. This report is intended to provide a high-level overview of the proposed works to support the resource consent and further technical details can be found in the associated reports:

- 1 Contaminated land preliminary and detailed site investigation<sup>4</sup>
- 2 Ecological opportunities and constraints<sup>5</sup>
- 3 Hydraulic flood model build<sup>6</sup>
- 4 Flood effects assessment<sup>7</sup>
- 5 Geotechnical factual report<sup>8</sup>
- 6 Geotechnical interpretive report<sup>9</sup>
- 7 Stormwater assessment<sup>10</sup>
- 8 Transportation design report<sup>11</sup>

### 1.1 Project aim and objective

T+T has been supporting HBRC with a variety of activities since Cyclone Gabrielle in February 2023. Part of this work has involved T+T undertaking a review of potential flood mitigation options for land previously categorised as 2C near the Omāhu area<sup>12</sup>. During Cyclone Gabrielle, out of channel flows from the Okawa Stream flooded the Omāhu and Ohiti Rd settlements. Further background, including a summary of the flood mechanisms are provided in our 2024 concept design report<sup>13</sup>. Figure 1.1

<sup>1</sup> Tonkin & Taylor Ltd (27 June 2023). Letter of Engagement. HBRC Land Categorisation - Proposal for technical support for mitigation options assessment. T+T Ref. 1017353.2301.

<sup>2</sup> Tonkin & Taylor Ltd (September 2021). Variation Order (VO3) - HBRC Ohiti Road Stopbank – Variation Order 3- Design Scope. T+T ref: 1017353.2101.

<sup>3</sup> Tonkin & Taylor Ltd (24 July 2025). Ohiti Road (Omahu) Flood Protection Stopbank Works, Preliminary Design Report, T+T Job No: 1017353.2402.

<sup>4</sup> Tonkin & Taylor Ltd (July 2025). Ohiti Road Stopbanks, Preliminary and detailed site investigations, T+T Job No: 1017353.2402.

<sup>5</sup> Tonkin & Taylor Ltd (May 2025). Ecological Opportunities and Constraints Assessment, T+T Job No: 1017353.2402

<sup>6</sup> Tonkin & Taylor Ltd (July 2024). Okawa Stream Hydraulic Model Build, T+T Job No: 1017353.2402

<sup>7</sup> Tonkin & Taylor Ltd (July 2025). Consequential Flood Effects of the Omāhu Stopbanks, T+T Job No: 1017353.2402

<sup>8</sup> Tonkin & Taylor Ltd (June 2025). Ohiti and Taihape Stopbank, Factual Report, T+T Job No: 1017353.2402

<sup>9</sup> Tonkin & Taylor Ltd (July 2025). Ohiti Road (Omahu) Flood Protection Stopbank Works - Geotechnical Interpretive Report, T+T Job No: 1017353.2402

<sup>10</sup> Tonkin & Taylor Ltd (July 2025). 18/20 Ohiti Road, Flood Protection Works Drainage mitigation measures, T+T Job No: 1017353.2402

<sup>11</sup> Tonkin & Taylor Ltd (July 2025). Ohiti and Taihape Roads Stopbank, Preliminary Transport Design Report, T+T Job No: 1017353.2402

<sup>12</sup> HBRC Land Categorisation - Proposal for technical support for mitigation options assessment, 27 June 2023, T+T Job No: 1017353.2301.

<sup>13</sup> Tonkin & Taylor Ltd (26 January 2024). Omāhu Stopbank Concept Design Review, T+T Job No: 1017353.2301.

illustrates the flood water observation extents that were mapped by HBRC following the February 2023 Cyclone Gabrielle event<sup>14</sup>.



Figure 1.1: Hawke's Bay flood observation extents for the February 2023 Cyclone Gabrielle event, as shown on the Hawke's Bay Regional Council website<sup>14</sup>.

The project's aim is to provide 100-year Average Recurrence Interval (ARI) flood protection to the properties south of Taihape Road and within the Ohiti and Omāhu areas, as identified in Figure 2.2 below. This assessment has been completed considering a 2050 Representative Concentration Pathway (RCP) 8.5 climate change scenario for the Okawa Stream, and concurrent present day 100-year ARI for the Ngaruroro River (3,925 m<sup>3</sup>/s at the Ngaruroro Fernhill flow recorder site), along with a 700 mm freeboard to inform the stopbank preliminary design. However, we understand that HBRC may propose some amendments to these, any changes will be reflected in the detailed design package once confirmed. This will move the community from provisional Category 2C – which demands community-level interventions for managing potential severe weather risks – to Category 1. Further details on the Land Categorisation process have been defined by multiple reports by HBRC and Pattle Delamore Partners (PDP).

The 2C portion of land has an area of 19 ha and includes the Ohiti Road subdivision, as shown below in Figure 2.1 and can be viewed in more detail on the Hastings District Council land categorisation maps<sup>15</sup>. Another smaller portion of Omāhu (single property north of Taihape Road (222 Taihape Road)) falls under Category 3 and sits outside of the proposed works. As such, the proposed mitigation measures will not address the future flood risks at this property.

<sup>14</sup> Hawke's Bay Regional Council, website: <https://www.hbrc.govt.nz/our-council/cyclone-gabrielle-response/cyclone-gabrielle-flooding/>

<sup>15</sup> <https://www.hastingsdc.govt.nz/assets/Document-Library/Cyclone-Land-Categorisation-Hastings-and-Napier/Omahu-6-Nov-2023-1.pdf>

## 2 Site location and description

Ohiti and Omāhu areas are located to the northwest of Hastings on the north (left) bank of the Ngaruroro River. The Ohiti settlement has been developed on a flat terrace located south of both Taihape Road and the Okawa Stream. The Omāhu settlement has been developed either side of Taihape Road and north of Okawa Stream. Most dwellings are located on a flat terrace feature, with a few properties located further north within the adjacent hills.

The Okawa stream headwaters are north of the subject site near Okawa homestead, before running south, crossing over Taihape Road twice upstream of the site. The Okawa stream has an overflow channel into Runanga Lake (northwest of the 2C area) before its confluence with the Ngaruroro River, southeast of both areas. The Ohiti and Omāhu areas are connected via the Taihape Road Bridge. The Okawa stream is also referred to as the Ohiwa stream in some historical information, although HBRC maps refer to the stream as the Okawa Stream. In this report it is referred to as Okawa stream, except where historical information is being directly quoted. Figure 2.1 below illustrates key water features along with the Okawa Stream flow path.




Figure 2.1: Okawa Stream flow path and nearby water bodies.

The Ngaruroro River flows west to east, south of both the Ohiti and Omāhu areas. The southern boundary of the Ohiti settlement sits behind a natural terrace feature that sits above the river, and an existing stopbank runs from Taihape Road south of the Omāhu settlement and along the banks of the Ngaruroro River further east.

A plan of the affected Ohiti and Omāhu areas with the key features marked out can be seen below in Figure 2.2 (refer also preliminary design drawings included in Appendix A).



Figure 2.2: Ohiti and Omāhu areas along with key features.

## 2.1 Site history and background

The Ohiti and Omāhu areas have experienced many historical flooding events, with some notable recent events listed from oldest to most recent below<sup>16</sup>.

- April 1897 North Island flooding - Flooding at Omāhu caused property damage, houses to be washed away, damage to crops and fences and three men drowned at Ohiti.
- June 1917 Hawke's Bay flooding - There was major flooding in Omāhu resulting in serious stock losses.
- March 1924 Hawke's Bay flooding - Omāhu flooded when the Ngaruroro River overflowed.
- April 1938 Gisborne and Hawkes Bay Flooding-Heavy rainfall reported but no historical notes of flooding in the catchment.
- April 1968 New Zealand ex-tropical Cyclone Giselle - Surface flooding occurred for some days in the Omāhu area.
- September 1988 North Island Cyclone Bola - There was a lot of surface flooding and scouring of the banks of the Okawa.

Stopbank schemes have been present on the Ngaruroro since the early 1900s. Much of the northwestern side of the Chesterhope Upper stopbanks were constructed in the 1960s, with some downstream areas, towards Omāhu township and SH50 being upgraded in the late 1980s and 1990s following the 1987 scheme review. Based on our understanding, there were no recent upgrade works to this section as part of the 1990s refurbishment programme.

<sup>16</sup> Niwa Historic Weather Events - <https://niwa.co.nz/climate/our-services/obtaining-climate-data-from-niwa>

### 2.1.1 Flood Levels during Cyclone Gabrielle

In total, 153 houses were affected by flooding during Cyclone Gabrielle in the wider Ohiti and Omāhu areas<sup>17</sup>. Some of these include houses damaged east of the subject site, due to stopbank breaches by the SH50 bridge at Fernhill. From discussions with community, it is understood the water levels on the Okawa stream during Cyclone Gabrielle were raised to just over deck level of Taihape Road bridge, which sits at approximately 29 metres RL. The houses affected by flooding shown in the red 2C box also sit at 29 metres RL. Houses located at 29.5 metres RL and higher were unaffected, as shown in Figure 2.3 below. We understand that properties within the Omāhu site area were impacted by floodwaters breaking out from Okawa Stream and flowing east, meeting the flows from the breach at SH50 bridge around Omāhu School.



Figure 2.3: Contour information based on 2020 LINZ LiDAR.

## 3 Design inputs and assumptions

### 3.1 Survey data

HBRC provided T+T with drone survey data collected for the Ohiti Road (Omāhu) Flood Protection Stopbank Works by 'The Surveying Company' in February 2024. All data provided to T+T was converted to the survey datum NZTM2000 for horizontal and NZVD2016 for vertical. These datums have been used on all drawings and models for the stopbank and stream design.

Various other infill survey have been completed by Civil Services (HB) Ltd on behalf of HBRC and provided to T+T for particular elements (culverts and stream banks etc).

### 3.2 Hydrology

T+T's hydrology assessment is summarised in the 2024 hydraulic model build report<sup>6</sup>.

### 3.3 Existing infrastructure

Chorus (telecommunications) and Unison (electricity) have been provided draft plans showing where the proposed works may interfere with their assets. Chorus have indicated that their underground

<sup>17</sup>NZ Herald, 10 September 2023, Omāhu Marae to host temporary homes for cyclone-hit whānau, [https://www.nzherald.co.nz/hawkes-bay-today/news/omahu-marae-to-host-temporary-homes-for-cyclone-hit-whanau/7ENDM6JIGJA7JOHCSZQVJTJBKY/#google\\_vignette](https://www.nzherald.co.nz/hawkes-bay-today/news/omahu-marae-to-host-temporary-homes-for-cyclone-hit-whanau/7ENDM6JIGJA7JOHCSZQVJTJBKY/#google_vignette).

fibre may need to be rerouted along the road raising of Taihape Road. Unison is yet to provide feedback. Integration of the utilities into the embankment and road design will be made at the detailed design stage. The existing utilities are shown on drawings 1017353.2402-TT-811 and 821.

The locations of private assets are not publicly available and are generally not expected to be encountered within the proposed works. This will be further reviewed at both the detailed design and pre-construction phases.

We understand that Hastings District Council will review roading requirements/Engineering Approvals as part of the consenting process. Provision will be required to ensure that road traffic can be accommodated during construction. This may require a temporary bypass (not shown on the attached drawings).

### **3.4 Scope of work**

The scope of work can be categorised under the following sections:

#### **3.4.1 Stopbank Design – overtopping considerations**

Flood modelling has been undertaken to inform the design crest level of the stopbank. This has been undertaken by T+T using the Okawa stream model. The stopbank crest sits at a 700 mm freeboard level above the modelled 100-year ARI flood level considering a climate change RCP8.5 2050 scenario for the Okawa Stream and present day 100-year ARI for the Ngaruroro River. Final freeboard levels will be confirmed during detailed design but will not exceed these levels. It is anticipated that crest levels and freeboard will stay the same or be reduced at detailed design.

#### **3.4.2 Stopbank Design – geotechnical aspects**

The scope of the design work has included geotechnical analyses of liquefaction, stability and seepage under 100-year ARI design considerations, broadly consistent with HBRC's IRG (prior to Cyclone Gabrielle) project technical briefs (in lieu of a specific technical brief from the client).

Geometric design of the stopbank has been completed including earthworks levels, grades and cut/fill requirements.

#### **3.4.3 Okawa Streamworks**

HBRC commissioned T+T to complete the design of rock armour works under the Taihape Rd bridge in late 2024. The works were completed as a permitted activity under HBRC Rule 70. The works were completed in early to mid-2025, including rock revetments, cut to waste earthworks and vegetation clearance. Additionally, further works have been completed upstream of the Taihape Rd bridge, on the Okawa stream, including channel clearance, willow trimming, rock revetments and soft landscaping.

As these works are substantially complete at the time of writing, we have not referred to these any further. The hydraulic model created for the Ohiti Rd project considers the post streamworks channel geometry and roughness.

### 3.5 Consent framework

Regulatory relief in the form of Orders in Council (OiC) have been sought for the Ohiti Road (Omāhu) Flood Protection Stopbank Works Project and other flood mitigation projects in the land categorisation programme. These provide a controlled activity status for the works. The project currently spans land both in and outside of areas considered within the OiC. As such the project will be consented under a bespoke framework considering both the OiC (including agreed conditions) and the RMA. Further discussion on how these conditions are met is discussed further at Section 9. Stradegy Planning Limited (Stradegy) are preparing the consenting applications.

## 4 Stopbank preliminary design

T+T has previously issued an Omāhu Stopbank Concept Design Review report<sup>13</sup> and Okawa Stream Hydraulic Model Build report<sup>6</sup>, which provide background and context to the current design solution. This report builds on the information presented in these reports, and as such they should be referenced for further background information.

The preliminary proposed Ohiti Road (Omāhu) Flood Protection Stopbank Works considered in this report are illustrated in Figure 4.1. The key design aspects for the development are summarised below, with the previously referenced technical reports. Works include:

- Stopbanking around Ohiti Rd to provide flood protection to the community in the Category 2 area (up to a 100-year ARI RCP8.5 2050 climate change scenario considering a 700 mm freeboard). As noted above final freeboard levels will be confirmed during detailed design but will not exceed these levels.
- Continuation of the stopbanks around the southern side of the properties to provide protection from the Ngaruroro River (up to a 100-year ARI level, with no climate change allowance and 700 mm freeboard).
- Raising of Ohiti Rd over the stopbank.
- Construction of a culvert and swale at the southwestern end of the site where overland flow paths will be captured and directed east to the Ngaruroro River.
- Various stormwater works, to facilitate local drainage.
- Rehabilitation and raising of the northern end of the Chesterhope Upper stopbank to achieve sufficient crest levels to mitigate the effects of the Ohiti Rd stopbanks (up to a 100-year ARI RCP8.5 2050 climate change scenario considering a 700 mm freeboard).
- Raising Taihape Rd over the extended and raised stopbanks.

The set of preliminary design drawings are presented within Appendix A.




Figure 4.1: Preliminary design indicating key features of the Ohiti Road (Omāhu) Flood Protection Stopbank Works.

#### 4.1 Flood model

The hydraulic model<sup>6</sup> and consequential flood effects<sup>7</sup> of the flood protection works have been presented within standalone reports, and should be referred to for the complete information on the flood model and associated effects considered within the preliminary design.

In summary, the project currently adopts a 100-year ARI RCP8.5 2050 climate change scenario for the flood modelling of Okawa Stream and present day 100-year ARI flood levels for the Ngaruroro River. A sensitivity assessment considering an estimated Cyclone Gabrielle event was also undertaken. A freeboard of 700 mm has been considered on both models to inform the stopbank crest levels.

Largely, the model remains unchanged from the original model build as presented in the model build report<sup>6</sup> except for changes following an external peer review and with newly available information being incorporated.

Flood hazard assessments were undertaken using the Okawa Stream hydraulic model, for several model scenarios, both with and without the proposed stopbanks. The model indications that water levels increase by up to 600 mm upstream of the stopbanks. Flood levels decrease within the subdivision at Ohiti Road and east along Taihape Road in both the 100-year ARI RCP8.5 2050 and estimated Cyclone Gabrielle event (tailwater level set by the estimated present day 100-year ARI flood levels for the Ngaruroro River).

The model indicates that the number of building footprints subject to flood hazard reduces significantly in the 100-year ARI with the RCP8.5 2050 climate event (tailwater level set by the estimated present day 100-year ARI flood levels for the Ngaruroro River). In the estimated Cyclone Gabrielle event, the reduction in the number of building footprints subject to hazard diminishes as the proposed stopbank is overtopped, resulting in similar flooding to the base case scenario.

## 4.2 Design functional requirements summary

At the direction of HBRC, the design includes 1V:2.5H batter slopes along the length of the proposed stopbanks, with the exception of Ch 0 to approximately Ch 140 along the Chesterhope Upper Stopbank, where due to a narrow easement allowance the batter is steepened to 1V:1.8H to limit encroachment on the surrounding private properties. The steeper batter section will need to additional reinforcement, such as DuraSlope Reinforced Soil System by Cirtex, to provide sufficient stability.

A crest width of 4 m has generally been considered along all of the stopbanks, again with the exception of Ch 0-140 of the Chesterhope Upper Stopbank where a reduced width of 2 m has been considered in order to meet the space constraints to fit within the existing easement. HBRC will need to consider maintenance requirements in this section, as it is unlikely to allow vehicle movement along this short length.

Proposed design levels suggest in some areas where stopbanks are already existing, that a nominal adjustment is required in order to meet new crest level requirements. Actual requirements will be refined at detailed design in order to identify whether additional fill will be required or if the current form is sufficient. Where the existing stopbank condition is insufficient a nominal depth may be proposed to be reconstructed to provide further resilience. The stopbank form will be optimised and clarified at detailed design.

During detailed design, the stopbank footprint will be reviewed for local features, such as boundary fencing, and set out points confirmed prior to construction works. Further detailing of the reinforcement will also be required. Permanent access points and maintenance requirements should be confirmed at detailed design.

## 5 Transport

A transport design report<sup>11</sup> has been prepared to address the transportation changes required to enable the stopbank works, specifically localised geometric adjustments of the existing alignments of Ohiti and Taihape Roads where the stopbank crosses their path.

The roading design includes the following key elements:

- 1 Ohiti Road vertical geometry adjustment over one section of the stopbank;
- 2 Taihape Road vertical geometry adjustment over one section of the stopbank;
- 3 Taihape Road Horizontal geometry curve realignment easing;
- 4 A separate access road to a number of properties along the southern side of Taihape Road;
- 5 Reconstruction of joint rural property access north of Taihape Road;
- 6 Accommodation for a known school bus collect / drop-off area; and
- 7 Pavement design.

The roading design was undertaken ensuring the design provided a safe facility for all road users and minimising the impact on affected landowners. The transport design report should be referred to for the complete assessment and analysis.

It is of note that the current design for access to the eastern dwellings of the Ohiti settlement retains the existing location and layout. We understand this is preferred by the residents as it retains the existing access point and only involves minor changes to the driveway crossing. We understand that driveway gradients may be undesirable from a headlight glare perspective, but we understand that this is acceptable by the residents and that the landscape architect will position planting to reduce impacts.

## 6 Geotechnical

Geotechnical investigations were carried out at the site over 2024 and 2025, the results of which are presented in the Ohiti and Taihape Stopbank Factual Report<sup>8</sup> which was initially issued in early 2024 and subsequently updated following additional investigations, with the latest issue dated June 2025. This report should be referred to for the factual presentation of the site investigation information.

This information has been used as the basis of the Ohiti Road (Omahu) Flood Protection Stopbank Works - Geotechnical Interpretive Report<sup>9</sup> which presents the geotechnical design information for the proposed works. This report should be referred to for the detailed geotechnical assessment and full considerations, however a summary of the report is provided below.

In summary, the foundation conditions generally consist of Holocene alluvial sediments, and two distinct geological zones have been identified across the project area:

- Zone one: Thick layer of Holocene alluvial sands, silts and clays overlying gravel and sand mixtures, with the Petane (limestone) Formation located beneath. This is generally located below the Ohiti stopbank, however, some isolated areas of Zone two soils also exist here as discussed below.
- Zone two: Thin layer of Holocene alluvial sands and silts overlying a thick sandy gravel layer. This is located below the Chesterhope Upper stopbank, and in two isolated locations to the east and southwest of the Ohiti stopbank. The geotechnical interpretive report should be referred to for further detail.

The stopbank performance was assessed in line with the required conditions specified by HBRC. The analyses indicates that:

- Stopbanks should be constructed from Unit 1A (silty sand) materials sourced from the borrow pit.
- The use of Unit 1B (gravel materials) is generally not suitable as stopbank fill in the current stopbank form. The use of this unit will be explored further at the detailed design stage if needed.
- Under static conditions the stopbank slopes generally have an adequate factor of safety.
- Insignificant to moderate liquefaction-induced damage is expected under ILS and ULS seismic loading. Liquefaction and lateral spreading are within HBRC design tolerances, and no ground improvement is proposed. No damage is expected under SLS shaking.
- Static consolidation settlements under a typical embankment load could be in the order of 0 to 150 mm over a 50 year time period. We expect that most of this would occur immediately following construction (i.e. within a matter of several days to weeks) but long-term settlement of up to 80 mm could occur over time. Static settlement is expected primarily in Zone 1, where softer soil layers (Units 2B and 2C) are present. The effect of settlement on the stopbank crest levels during and post construction will be considered further at detailed design.
- Between Chainage 80 – 140 at the Chesterhope Upper stopbank, batter slopes steepen to approximately 1V:1.8H. To mitigate erosion risks and promote vegetative growth on these steepened slopes, the use of reinforcement matting is recommended.

### 6.1 Borrow materials

The proposed stopbank fill material is to be sourced from the onsite borrow pit located approximately 400 m east of the proposed Ohiti Stopbank and 250 m south of the Chesterhope Upper stopbank and as indicated on Figure 4.1. The borrow material consists predominantly of silt and sand mixtures overlying sandy gravels with cobbles.

The borrow pit will be prepared by:

- 1 Stripping the topsoil and storing appropriately onsite;
- 2 Constructing a bund around the borrow pit extents to control runoff (other runoff measures may also be required, and management throughout the operations will need to be considered);
- 3 Material to be cut from the borrow area in sections to minimise the exposed soil;
- 4 Material to be carted to stopbanks for use in construction;
- 5 Once the full depth of soil extraction has been completed the contractor to move to next section. At completion of each section area to be retopsoiled. At completion of works, bunds to be constructed to encourage siltation and backfilling of pit.

## 6.2 Geotechnical considerations for construction

The following will need to be considered during the detailed design and construction phase of the project, with respect to geotechnical matters:

- 1 Borrow material extraction will need to be monitored to ensure materials are consistent with those assumed in design.
- 2 Foundation materials to be reviewed along the alignment to ensure they are consistent with that assumed in the design. During the detailed design process, the final extent of the undercutting works will need to be confirmed.
- 3 Generally, it is not expected that groundwater will be encountered during the stopbank foundation preparation. However, subject to weather conditions at the time area of higher groundwater may be encountered, during which time pumping and drainage measures may be necessary.
- 4 An earthworks specification will be prepared for the project, outlining the compaction requirements and treatment of foundation soils and stopbank fill.
- 5 Geotechnical oversight of foundation treatment and fill compaction will be required throughout the earthworks process.
- 6 Generally, the proposed fill and foundation soils are compatible. However, we recommend further assessment of the filter compatibility between some of the fill/foundation soil combinations are refined at detailed design.

## 7 Culverts, swales and stormwater management

The construction of the stopbanks will interrupt the existing stormwater flows across the site in various locations. A selection of new culverts and swales are proposed to manage stormwater flows inline with HBRC requirements. The flood protection works drainage mitigation measures report<sup>10</sup> outlines the effected areas and proposed solutions to mitigate any effects.

In summary, current stormwater runoff from a catchment west of 18/20 Ohiti Road historically flows north of Taihape Road to 222 Taihape Road and into the Okawa stream. The proposed stopbank south of Taihape Road will block this flow path and as a result increase the flood risk to this property. The flood protection works drainage mitigation measures report presents an alternative drainage solution to convey stormwater through a series of culverts and swales east of the property and into the Okawa stream.

South of the Ohiti settlement, stormwater flows will be channelled towards a new scruffy dome within the western road reserve of Ohiti Road and directed to a new swale that runs west to east and designed to intercept any other flows that are flowing towards the Ohiti settlement. The swale conveys intercepted water to the banks of the Ngaruroro River.

The culvert located below the existing driveway at 170 Taihape Road will be upgraded to provide drainage to the area between the shared driveway and the new stopbank, north of Taihape Rd. In this location, the ground levels are very flat and further survey will be required to establish ground levels east of the driveway. The preference from HBRC is to construct a culvert to outlet to the Okawa to the east of the site. However, this may require outletting through the recently completed rock revetment works. An alternative would be to run the culvert under Taihape Rd to the southwest, however, this will require confirmation with the landowners and potentially an easement and localised swale/shaping works. This will be confirmed at detailed design.

The proposed drainage works are illustrated in Figure 7.1, and the drainage mitigation measures report should be referred to for further details.




Figure 7.1: Approximate location of the Ohiti and Omāhu stopbanks, culverts and swales.

## 8 Erosion and sediment controls

Erosion and sediment controls will need to be confirmed by the contractor during the pre-construction process prior to works commencing. The contractor should consider:

- 1 Silt fencing around working areas and progressive stabilisation of stopbank faces and the borrow pit with topsoil and grass. It may be appropriate to limit the open areas of earthworks to limit the extent of exposed faces.
- 2 Erosion control devices should be considered where large open earthworks faces are proposed. This may include decanting earth bunds, clean and dirty water diversion bunds or sediment ponds.
- 3 Topsoil should be 'worked into' the stopbank face and track rolled with a bulldozer or similar. HBRC have a nominated subcontractor and grass mix for approved use on stopbank sites.

- 4 Dust suppression will need to be considered, due to the fine sand and silt soils within the river berms. Water carts, sprinkler systems or similar should be considered by the Contractor. However, in some cases it may be appropriate to cover exposed faces with topsoil or aggregate.
- 5 Haul roads should be stabilised with gravel to minimise dust and sediment generation.
- 6 Accessways to and from local roads should be managed to mitigate soil being transported onto roadways.
- 7 Consideration for ford or crossing details, if vehicles intend to haul from the borrow pit and cross the stream to the Chesterhope upper stopbanks.  
Stormwater management during the works and management around the water bore at 170 Taihape Road (and any others).

## 9 Consenting

Included in Appendix B is a table describing the standardised OIC conditions of consent and the corresponding design intent proposed to meet the consent conditions.

## 10 Conclusions

The Ohiti Road (Omāhu) Flood Protection Stopbank Works aims to significantly reduce flood risks to the Ohiti and Omāhu settlements by constructing new stopbanks to provide additional protection from flows from the Okawa Stream and Ngaruroro River.

The stopbank design has been based on flood modelling developed by T+T for HBRC. The stopbank is designed to contain a 100-year ARI event considering a RCP8.5 2050 climate change scenario for the Okawa Stream and present day 100-year ARI flood level for the Ngaruroro River. A freeboard of 700 mm has been considered above these levels to inform the stopbank crest levels. We do understand that HBRC are reevaluating the design case and any updates will be captured within the detailed design stage of the project.

Stopbanks have generally been designed with 1V:2.5H batter slopes, with the exception of the northwestern end of the Chesterhope Upper stopbank which incorporates a steeper 1V:1.8H batter to fit within the existing easement. Stopbanks are to be constructed from material extracted from the nearby borrow site, with appropriate conditioning and with materials (gravels or silty sands) selected based on grain size and design requirements.

In order to accommodate the stopbanks both Ohiti Road and Taihape Road need to be raised locally to accommodate the stopbanks passing below. Property accessways also need to be raised and realigned to accommodate the proposed works.

New stormwater infrastructure inclusive of new culverts and swales have been incorporated into the design to ensure adequate drainage exists around the settlements and accessways.


## 11 Applicability

This report has been prepared for the exclusive use of our client Hawke's Bay Regional Council, with respect to the particular brief given to us and it may not be relied upon in other contexts or for any other purpose, or by any person other than our client, without our prior written agreement.

Tonkin & Taylor Ltd  
Environmental and Engineering Consultants

Report prepared by:

Authorised for Tonkin & Taylor Ltd by:



Regan King  
Senior Geotechnical Engineer



Tim Morris  
Project Director

Report reviewed by:



Jamie Yule  
Project Manager

\\ttgroup.local\corporate\wellington\tt projects\1017353\1017353.2402\issueddocuments\20250903 summary of design for resource consent purposes\1017353.2402-rpt-gg-orfps-009 summary of design for resource consent purposes.docx


# **Appendix A      Preliminary Design Drawings**

---

### DRAWING LIST

	DRAWING NUMBER	REV	TITLE
GENERAL			
1	1017353.2402-TT-001	4	DRAWING LIST AND LOCATION PLAN
PLAN			
2	1017353.2402-TT-010	4	OVERALL PLAN
3	1017353.2402-TT-011	4	OHITI ROAD AND STOPBANK - LAYOUT PLAN
4	1017353.2402-TT-012	4	OHITI ROAD AND STOPBANK - CUT AND FILL
5	1017353.2402-TT-013	2	OHITI ROAD AND STOPBANK - DESIGN CONTOURS
6	1017353.2402-TT-021	4	TAIHAPE ROAD AND STOPBANK - LAYOUT PLAN
7	1017353.2402-TT-022	4	TAIHAPE ROAD AND STOPBANK - CUT AND FILL
8	1017353.2402-TT-023	2	TAIHAPE ROAD AND STOPBANK - DESIGN CONTOURS
9	1017353.2402-TT-027	2	BORROW AREA SITE PLAN
ROADING SECTIONS			
10	1017353.2402-TT-031	4	OHITI ROAD ALIGNMENT LONG SECTION
11	1017353.2402-TT-033	4	OHITI ROAD CROSS SECTIONS - SHEET 1
12	1017353.2402-TT-034	4	OHITI ROAD CROSS SECTIONS - SHEET 2
13	1017353.2402-TT-041	4	TAIHAPE ROAD ALIGNMENT LONG SECTION - SHEET 1
14	1017353.2402-TT-042	4	TAIHAPE ROAD ALIGNMENT LONG SECTION - SHEET 2
15	1017353.2402-TT-043	4	TAIHAPE ROAD CROSS SECTION - SHEET 1
16	1017353.2402-TT-044	4	TAIHAPE ROAD CROSS SECTION - SHEET 2
17	1017353.2402-TT-045	4	TAIHAPE ROAD CROSS SECTION - SHEET 3
18	1017353.2402-TT-046	4	TAIHAPE ROAD CROSS SECTION - SHEET 4
19	1017353.2402-TT-048	2	ACCESS ROAD SECTION
20	1017353.2402-TT-051	4	TYPICAL SECTIONS - SHEET 1
21	1017353.2402-TT-052	4	TYPICAL SECTIONS - SHEET 2
STOPBANK SECTIONS			
22	1017353.2402-TT-071	4	OHITI STOPBANK LONG SECTION - SHEET 1
23	1017353.2402-TT-072	4	OHITI STOPBANK LONG SECTION - SHEET 2
24	1017353.2402-TT-073	4	OHITI STOPBANK LONG SECTION - SHEET 3
25	1017353.2402-TT-074	4	OHITI STOPBANK CROSS SECTION - SHEET 1
26	1017353.2402-TT-075	4	OHITI STOPBANK CROSS SECTION - SHEET 2
27	1017353.2402-TT-076	4	OHITI STOPBANK CROSS SECTION - SHEET 3
28	1017353.2402-TT-077	4	OHITI STOPBANK CROSS SECTION - SHEET 4
29	1017353.2402-TT-078	4	OHITI STOPBANK CROSS SECTION - SHEET 5
30	1017353.2402-TT-081	4	CHESTERHOPE UPPER STOPBANK LONG SECTION
31	1017353.2402-TT-082	4	CHESTERHOPE UPPER STOPBANK CROSS SECTION - SHEET 1
32	1017353.2402-TT-083	4	CHESTERHOPE UPPER STOPBANK CROSS SECTION - SHEET 2
33	1017353.2402-TT-091	2	TYPICAL CROSS SECTIONS - CHESTERHOPE
34	1017353.2402-TT-092	2	TYPICAL SECTION - OHITI

	DRAWING NUMBER	REV	TITLE
ROADING AND TRANSPORT			
35	1017353.2402-TT-541	2	SIGNAGE AND ROAD MARKINGS PLAN - SHEET 1
36	1017353.2402-TT-542	2	SIGNAGE AND ROAD MARKINGS PLAN - SHEET 2
37	1017353.2402-TT-543	2	SIGNAGE AND ROAD MARKINGS PLAN - SHEET 3
38	1017353.2402-TT-551	4	TAIHAPE ROAD - VEHICLE TRACKING PLAN
39	1017353.2402-TT-571	4	TAIHAPE ROAD - SIGHT DISTANCE PLAN
STORMWATER			
40	1017353.2402-TT-611	2	CULVERT LAYOUT PLAN - OHITI ROAD
41	1017353.2402-TT-621	2	CULVERT LAYOUT PLAN - TAIHAPE ROAD
42	1017353.2402-TT-631	2	CULVERT LAYOUT PLAN - SMITH PROPERTY
43	1017353.2402-TT-651	2	CULVERT - LONG SECTIONS
44	1017353.2402-TT-661	2	SMITH PROPERTY CULVERT / SWALE LONG SECTION
45	1017353.2402-TT-671	2	TAIHAPE ROAD ACCESS TRACK SECTION
UTILITIES			
46	1017353.2402-TT-811	2	UTILITIES PLAN - OHITI ROAD
47	1017353.2402-TT-821	2	UTILITIES PLAN - TAIHAPE ROAD
	Ü		DENOTES DRAWINGS IN THIS ISSUE: 19/08/2025



NOTE: TOPOMAP SOURCED LINZ DATA SERVICE. <https://data.linz.govt.nz/layer/50767-nz-topo50-maps/>, LICENSED BY LINZ FOR RE-USE UNDER THE CREATIVE COMMONS ATTRIBUTION 4.0 INTERNATIONAL

**LOCALITY PLAN**  
SCALE (A1) N.T.S.  
SCALE (A3) N.T.S.



www.tonkintaylor.co.nz

1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS PRELIMINARY	CLIENT <b>HAWKES BAY REGIONAL COUNCIL</b>		
2	PRELIMINARY DRAFT	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25			PROJECT PHASE PRELIMINARY DESIGN	PROJECT <b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25				
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25	SCALE (A1) N.T.S.	DWG No. 1017353.2402-TT-001		
REV DESCRIPTION					CAD CHK		DATE	APPROVED	DATE		

NOT FOR CONSTRUCTION



THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

**NOTES**

1. COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
2. AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
3. PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024. EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".
4. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.
5. NORTHERN EXTENT OF OHITI STOPBANK CREST LEVELS ARE CURRENTLY DESIGNED TO THE PREVIOUS 100-YEAR ARI 2075 RCP8.5 PLUS 700mm LEVELS. UPDATE TO 2050 LEVELS WILL SHOW AN APPROXIMATELY 300mm CREST LOWERING TO THE WEST AND 300mm CREST RAISING TO THE EAST. TO BE UPDATED AT DETAILED DESIGN.
6. EXISTING SERVICES SOURCED BY T+T FROM TRANSPower LTD, HASTINGS DISTRICT COUNCIL AND HAWKES BAY REGIONAL COUNCIL OPEN GIS DATA ON 10/07/2025.
7. ALL DRAWINGS ARE PRELIMINARY ONLY AND NOT ALL REQUIRED DETAILS ARE YET INCLUDED. FINAL LEVELS, EXTENTS AND LAYOUT SUBJECT TO CHANGE BASED ON FINALISED DESIGN CASE. TO BE CONFIRMED BY HRBC FOR DETAILED DESIGN.

**LEGEND**

- PROPERTY BOUNDARY
- 30--- EXISTING MAJOR CONTOUR (10m INTERVAL)
- EXISTING MINOR CONTOUR (5m INTERVAL)
- OHHV --- EXISTING OVERHEAD POWER LINES
- HAWKES BAY REGIONAL COUNCIL PROVISIONAL LAND CATEGORY 2C AREA
- HAWKES BAY REGIONAL COUNCIL OIC AREA
- HAWKES BAY REGIONAL COUNCIL EASEMENTS
- PROPOSED STOPBANK
- PROPOSED SWALE
- PROPOSED CULVERT
- PROPOSED HAUL ROAD



www.tonkintaylor.co.nz

REV	DESCRIPTION	CAD	CHK	DATE
1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25
2	PRELIMINARY DRAFT	ALPO	TIBR	18.03.25
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25

DESIGNED	TIBR	Jan.25	DRAWING STATUS
DRAWN	ALPO	Jan.25	PRELIMINARY
DESIGN CHECKED	JWY	21.08.25	PROJECT PHASE
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN

**NOT FOR CONSTRUCTION**

APPROVED DATE

**CLIENT HAWKES BAY REGIONAL COUNCIL**

**PROJECT OHITI ROAD FLOOD PROTECTION STOPBANK WORKS**

**TITLE PLAN OVERALL PLAN**

SCALE (A1) 1:2500      DWG No. 1017353.2402-TT-010      REV 4

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED



**NOTES**

- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
- AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
- PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TF-01.DWG" DATED 29/02/2024.
- EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBC Omahu Filtered.las".

**LEGEND**


- PROPERTY BOUNDARY
- HAWKES BAY REGIONAL COUNCIL OIC BOUNDARY
- EXISTING MAJOR CONTOUR (5m INTERVAL)
- EXISTING MINOR CONTOUR (1m INTERVAL)
- PROPOSED STOPBANK (SEE 1017353.2402-TT-013 FOR DESIGN CONTOURS)
- PROPOSED CULVERT
- PROPOSED SWALE
- PROPOSED ROAD EXTENT
- VEGETATION REMOVAL



1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25
2	PRELIMINARY DRAFT	ALPO	TIBR	18.03.25
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE

DESIGNED	TIBR	Jan.25	DRAWING STATUS <b>PRELIMINARY</b> PROJECT PHASE <b>PRELIMINARY DESIGN</b>
DRAWN	ALPO	Jan.25	
DESIGN CHECKED	JWY	21.08.25	
DRAWING CHECKED	WYHU	21.08.25	
<b>NOT FOR CONSTRUCTION</b>			THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED
APPROVED		DATE	


CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	PLAN <b>OHITI ROAD AND STOPBANK - LAYOUT PLAN</b>
SCALE (A1)	1:1250
DWG No.	1017353.2402-TT-011
REV	4



**CUT FILL DEPTH ANALYSIS**

LOWER VALUE	UPPER VALUE	COLOUR
-2.0	to -1.8	m
-1.8	to -1.6	m
-1.6	to -1.4	m
-1.4	to -1.2	m
-1.2	to -1.0	m
-1.0	to -0.8	m
-0.8	to -0.6	m
-0.6	to -0.4	m
-0.4	to -0.2	m
-0.2	to 0.0	m
0.0	to 0.2	m
0.2	to 0.4	m
0.4	to 0.6	m
0.6	to 0.8	m
0.8	to 1.0	m
1.0	to 1.2	m
1.2	to 1.4	m
1.4	to 1.6	m
1.6	to 1.8	m
1.8	to 2.0	m
2.0	to 2.2	m
2.2	to 2.4	m
2.4	to 2.6	m
2.6	to 2.8	m
2.8	to 3.0	m
3.0	to 3.2	m
3.2	to 3.4	m
3.4	to 3.6	m
3.6	to 3.8	m

TOTAL VOLUMES (m <sup>3</sup> )	
TOTAL CUT	4263
TOTAL FILL	30775
TOTAL BALANCE	26492



**NOTES**

- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
- AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
- PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
- EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HRC Omaha Filtered.las".
- FOR THE FULL EXTENT OF THE HAWKES BAY REGIONAL COUNCIL OIC AREA REFER TO DRAWING 1017353.2402-TT-010.

**LEGEND**

- PROPERTY BOUNDARY
- 30 EXISTING MAJOR CONTOUR (5m INTERVAL)
- EXISTING MINOR CONTOUR (1m INTERVAL)
- HAWKES BAY REGIONAL COUNCIL OIC BOUNDARY



REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE
1	PRELIMINARY DRAFT	ALPO	TIBR	18.03.25		
2	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25		
3	PRELIMINARY DESIGN ISSUE OIC AND LAND DATA	ALPO	JWY	08.08.25		
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25		

DESIGNED	STLP	Feb.25	DRAWING STATUS
DRAWN	ALPO	Feb.25	PRELIMINARY
DESIGN CHECKED	JWY	21.08.25	PROJECT PHASE
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN

**NOT FOR CONSTRUCTION** THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

**CLIENT HAWKES BAY REGIONAL COUNCIL**

**PROJECT OHITI ROAD FLOOD PROTECTION STOPBANK WORKS**

**TITLE PLAN**

**OHITI ROAD AND STOPBANK - CUT AND FILL**

SCALE (A1) 1:1250      DWG No. 1017353.2402-TT-012      REV 4




www.tonkintaylor.co.nz

1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGNED STLP Jul.25 DRAWN ALPO Jul.25 DESIGN CHECKED JWY 21.08.25 DRAWING CHECKED WYHU 21.08.25	DRAWING STATUS PRELIMINARY PROJECT PHASE PRELIMINARY DESIGN	CLIENT <b>HAWKES BAY REGIONAL COUNCIL</b> PROJECT <b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b> TITLE PLAN OHITI ROAD AND STOPBANK - DESIGN CONTOURS
	2	REVISED PRELIMINARY DESIGN	MLE	JWY			
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE	SCALE (A1) 1:1250      DWG No. 1017353.2402-TT-013      REV 2

NOT FOR CONSTRUCTION

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED



- NOTES**
- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
  - AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
  - PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
  - EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.ias".

- LEGEND**
- PROPERTY BOUNDARY
  - HBRC OIC BOUNDARY
  - HBRC EASEMENT BOUNDARY
  - EXISTING MAJOR CONTOUR (5m INTERVAL)
  - EXISTING MINOR CONTOUR (1m INTERVAL)
  - PROPOSED STOPBANK (SEE 1017353.2402-TT-021 FOR DESIGN CONTOURS)
  - PROPOSED SEALED ROAD EXTENT
  - PROPOSED ROAD CENTERLINE
  - PROPOSED GRAVEL ROAD EXTENT
  - PROPOSED CULVERT
  - PROPOSED SWALE
  - VEGETATION REMOVAL




REV	DESCRIPTION	CAD	CHK	DATE
1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25
2	PRELIMINARY DESIGN	ALPO	TIBR	18.03.25
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25

DESIGNED	TIBR	Jan.25	DRAWING STATUS
DRAWN	ALPO	Jan.25	PRELIMINARY
DESIGN CHECKED	JWY	21.08.25	PROJECT PHASE
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN

**NOT FOR CONSTRUCTION** THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

APPROVED	DATE

<b>CLIENT</b>	<b>HAWKES BAY REGIONAL COUNCIL</b>
<b>PROJECT</b>	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
<b>TITLE</b>	<b>PLAN</b>
	<b>TAIHAPE ROAD AND STOPBANK - LAYOUT PLAN</b>
<b>SCALE (A1)</b>	<b>1:1000</b>
<b>DWG No.</b>	<b>1017353.2402-TT-021</b>
<b>REV</b>	<b>4</b>



www.tonkintaylor.co.nz


REV	DESCRIPTION	CAD	CHK	DATE
1	PRELIMINARY DESIGN	ALPO	TIBR	18.03.25
2	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
3	PRELIMINARY DESIGN ISSUE OIC AND LAND DATA	ALPO	JWY	08.08.25
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25

DESIGNED	JWY	Feb.25	DRAWING STATUS
DRAWN	ALPO	Feb.25	PRELIMINARY
DESIGN CHECKED	JWY	21.08.25	PROJECT PHASE
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN

**NOT FOR CONSTRUCTION** THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

APPROVED	DATE

<b>CLIENT</b>	<b>HAWKES BAY REGIONAL COUNCIL</b>
<b>PROJECT</b>	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
<b>TITLE</b>	<b>PLAN</b>
	<b>TAIHAPE ROAD AND STOPBANK - CUT AND FILL</b>
<b>SCALE (A1)</b>	<b>1:1000</b>
<b>DWG No.</b>	<b>1017353.2402-TT-022</b>
<b>REV</b>	<b>4</b>



**HOLD**  
 STEEPENED SECTION TO BE FURTHER REFINED AT DETAILED DESIGN TO KEEP FOOTPRINT WITHIN EASEMENT. TRANSITION FROM 2M CREST WIDTH TO 4m WIDTH TO BE CONFIRMED AT DETAILED DESIGN

**HOLD**  
 EXTENT OF WORKS TO BE CONFIRMED AT DETAILED DESIGN. SUBJECT TO FINAL LEVELS WORKS MAY BE LIMITED TO RECONDITIONING OF EXISTING STOPBANK

**NOTES**

- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
- AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
- PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
- EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".

**LEGEND**

- PROPERTY BOUNDARY
- EXISTING MAJOR CONTOUR (5m INTERVAL)
- EXISTING MINOR CONTOUR (1m INTERVAL)
- PROPOSED MAJOR CONTOUR (1m INTERVAL)
- PROPOSED MINOR CONTOUR (0.5m INTERVAL)
- PROPOSED STOPBANK
- PROPOSED CULVERT
- PROPOSED SWALE



www.tonkintaylor.co.nz



DESIGNED	STLP	Jul.25	DRAWING STATUS	STLP	Jul.25	PRELIMINARY
DRAWN	ALPO	Jul.25	PROJECT PHASE	ALPO	Jul.25	PRELIMINARY DESIGN
DESIGN CHECKED	JWY	21.08.25		JWY	21.08.25	
DRAWING CHECKED	WYHU	21.08.25		WYHU	21.08.25	
NOT FOR CONSTRUCTION			THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED			
APPROVED	DATE		APPROVED	DATE		

1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE

CLIENT	HAWKES BAY REGIONAL COUNCIL
PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS
TITLE	PLAN TAIHAPE ROAD AND STOPBANK - DESIGN CONTOURS
SCALE (A1)	1:1000
DWG No.	1017353.2402-TT-023
REV	2

- NOTES**
- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
  - AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
  - PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
  - EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".

- LEGEND**
- PROPERTY BOUNDARY
  - EXISTING MAJOR CONTOUR (2.5m INTERVAL)
  - EXISTING MINOR CONTOUR (0.5m INTERVAL)
  - PROPOSED MAJOR CONTOUR (2.5m INTERVAL)
  - PROPOSED MINOR CONTOUR (0.5m INTERVAL)
  - PROPOSED SITE BOUNDARY
  - PROPOSED BORROW PIT TOE
  - PROPOSED BUND AREA



**SECTION 1**  
SCALE (A1) 1:500  
SCALE (A3) 1:1000



REV	DESCRIPTION	CAD	CHK	DATE
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25


DESIGNED	STLP	May.25	DRAWING STATUS
DRAWN	STLP	May.25	PRELIMINARY
DESIGN CHECKED	JWY	21.08.25	PROJECT PHASE
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN

**NOT FOR CONSTRUCTION** THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED


<b>CLIENT</b>	<b>HAWKES BAY REGIONAL COUNCIL</b>
<b>PROJECT</b>	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
<b>TITLE</b>	<b>PLAN</b>
	<b>BORROW AREA SITE PLAN</b>
<b>SCALE (A1)</b>	<b>AS SHOWN</b>
<b>DWG No.</b>	<b>1017353.2402-TT-027</b>
<b>REV</b>	<b>2</b>

**NOTES**


- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016.
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.



**1 LONG SECTION: OHITI ROAD - CHAINAGE 0 TO 175**  
 SCALE (A1) 1:250 (HORIZ), 1:125 (VERT)  
 SCALE (A3) 1:500 (HORIZ), 1:250 (VERT)



**1 LONG SECTION: OHITI ROAD - CHAINAGE 175 TO 260**  
 SCALE (A1) 1:250 (HORIZ), 1:125 (VERT)  
 SCALE (A3) 1:500 (HORIZ), 1:250 (VERT)



REV	DESCRIPTION	CAD	CHK	DATE	DESIGNED	SIDP	DATE	DRAWING STATUS
1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	SIDP	Jan.25	PRELIMINARY	
2	FOR REVIEW	ALPO	TIBR	18.03.25	ALPO	Jan.25	PRELIMINARY	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	TIBR	21.08.25	PROJECT PHASE	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	WYHU	21.08.25	PRELIMINARY DESIGN	










**NOT FOR CONSTRUCTION**

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

<b>CLIENT</b>	<b>HAWKES BAY REGIONAL COUNCIL</b>
<b>PROJECT</b>	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
<b>TITLE</b>	<b>ROADING SECTIONS OHITI ROAD ALIGNMENT LONG SECTION</b>
<b>SCALE (A1)</b>	<b>AS SHOWN</b>
<b>DWG No.</b>	<b>1017353.2402-TT-031</b>
<b>REV</b>	<b>4</b>

**NOTES**

1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.



1:100 (A1)  
1:200 (A3)




1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	SIDP	Jan.25	DRAWING STATUS PRELIMINARY PROJECT PHASE PRELIMINARY DESIGN
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	TIBR	21.08.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25	
					NOT FOR CONSTRUCTION			
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE		


<b>CLIENT</b>	<b>HAWKES BAY REGIONAL COUNCIL</b>
<b>PROJECT</b>	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
<b>TITLE</b>	<b>ROADING SECTIONS OHITI ROAD CROSS SECTIONS - SHEET 1</b>
<b>SCALE (A1)</b>	<b>1:100</b>
<b>DWG No.</b>	<b>1017353.2402-TT-033</b>
<b>REV</b>	<b>4</b>

**NOTES**


1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.




CHAINAGE 220




CHAINAGE 200



CHAINAGE 245



CHAINAGE 180



CHAINAGE 240



1:100 (A1)  
1:200 (A3)




www.tonkintaylor.co.nz

1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	SIDP	Jan.25	DRAWING STATUS	PRELIMINARY	
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	PRELIMINARY DESIGN	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	TIBR	21.08.25			
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25			
REV DESCRIPTION					CAD		CHK	DATE	APPROVED	DATE


NOT FOR CONSTRUCTION THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

CLIENT	HAWKES BAY REGIONAL COUNCIL
PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS
TITLE	ROADING SECTIONS OHITI ROAD CROSS SECTIONS - SHEET 2
SCALE (A1)	1:100
DWG No.	1017353.2402-TT-034
REV	4


- NOTES**
1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
  2. LEVEL DATUM: NZVD 2016.
  3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.



**LONG SECTION: TAIHAPE ROAD - PART ONE**  
 SCALE (A1) 1:250 (HORIZ), 1:125 (VERT)  
 SCALE (A3) 1:500 (HORIZ), 1:250 (VERT)



**1 LONG SECTION: TAIHAPE ROAD - PART TWO**  
 SCALE (A1) 1:250 (HORIZ), 1:125 (VERT)  
 SCALE (A3) 1:500 (HORIZ), 1:250 (VERT)



H=1:250  
 V=1:125



www.tonkintaylor.co.nz


1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	SIDP	Jan.25	DRAWING STATUS PRELIMINARY PROJECT PHASE PRELIMINARY DESIGN
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	TIBR	21.08.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25	
REV DESCRIPTION					CAD CHK DATE		APPROVED	DATE

**NOT FOR CONSTRUCTION** THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED


CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	ROADING SECTIONS TAIHAPE ROAD ALIGNMENT LONG SECTION - SHEET 1
SCALE (A1)	AS SHOWN
DWG No.	1017353.2402-TT-041
REV	4

**NOTES**


- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016.
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.



**1 LONG SECTION: TAIHAPE ROAD - PART THREE**  
 SCALE (A1) 1:250 (HORIZ), 1:125 (VERT)  
 SCALE (A3) 1:500 (HORIZ), 1:250 (VERT)



**1 LONG SECTION: TAIHAPE ROAD - PART FOUR**  
 SCALE (A1) 1:250 (HORIZ), 1:125 (VERT)  
 SCALE (A3) 1:500 (HORIZ), 1:250 (VERT)









DESIGNED	SIDP	Jan.25	DRAWING STATUS	PRELIMINARY		
DRAWN	ALPO	Jan.25	PROJECT PHASE	PRELIMINARY DESIGN		
DESIGN CHECKED	TIBR	21.08.25				
DRAWING CHECKED	WYHU	21.08.25				
NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED				
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE
1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25		
2	FOR REVIEW	ALPO	TIBR	18.03.25		
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25		
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25		

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	ROADING SECTIONS TAIHAPE ROAD ALIGNMENT LONG SECTION - SHEET 2
SCALE (A1)	AS SHOWN
DWG No.	1017353.2402-TT-042
REV	4



**NOTES**

1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.









1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	SIDP	Jan.25	DRAWING STATUS	PRELIMINARY	
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	PRELIMINARY DESIGN	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	TIBR	21.08.25			
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25			
REV DESCRIPTION					CAD		CHK	DATE	APPROVED	DATE

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	ROADING SECTIONS TAIHAPE ROAD CROSS SECTION - SHEET 2
SCALE (A1)	1:100
DWG No.	1017353.2402-TT-044
REV	4

**NOT FOR CONSTRUCTION** THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

**NOTES**

1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.



1:100 (A1)  
1:200 (A3)












REV	DESCRIPTION	CAD	CHK	DATE
1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25
2	FOR REVIEW	ALPO	TIBR	18.03.25
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25

DESIGNED	SIDP	Jan.25	DRAWING STATUS	PRELIMINARY
DRAWN	ALPO	Jan.25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	TIBR	21.08.25	NOT FOR CONSTRUCTION THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED	
DRAWING CHECKED	WYHU	21.08.25		
APPROVED		DATE		

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>		
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>		
TITLE	ROADING SECTIONS TAIHAPE ROAD CROSS SECTION - SHEET 3		
SCALE (A1)	1:100	DWG No.	1017353.2402-TT-045
REV	4		

**NOTES**

1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.




1:100 (A1)  
1:200 (A3)



www.tonkintaylor.co.nz

<ol style="list-style-type: none"> <li>1. PRELIMINARY DRAFT</li> <li>2. FOR REVIEW</li> <li>3. PRELIMINARY DESIGN ISSUE</li> <li>4. REVISED PRELIMINARY DESIGN</li> </ol>	ALPO	MGM	24.01.25	DESIGNED	SIDP	Jan.25	<b>DRAWING STATUS</b> PRELIMINARY <b>PROJECT PHASE</b> PRELIMINARY DESIGN THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED
	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	
	ALPO	JWY	24.07.25	DESIGN CHECKED	TIBR	21.08.25	
	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25	
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE	CLIENT <b>HAWKES BAY REGIONAL COUNCIL</b> PROJECT <b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b> TITLE <b>ROADING SECTIONS</b> <b>TAIHAPE ROAD CROSS SECTION - SHEET 4</b> SCALE (A1) 1:100      DWG No. 1017353.2402-TT-046      REV 4

- NOTES**
1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
  2. LEVEL DATUM: NZVD 2016.
  3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.




**1 LONG SECTION**  
 021 SCALE (A1) 1:500  
 SCALE (A3) 1:1000




www.tonkintaylor.co.nz

1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGNED	SIDP	Jul,25	DRAWING STATUS	CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWN	ALPO	Jul,25	PRELIMINARY	PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
2					DESIGN CHECKED	TIBR	21.08.25	PROJECT PHASE	TITLE	ROADING SECTIONS
					DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN		ACCESS ROAD SECTION
NOT FOR CONSTRUCTION					THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED			SCALE (A1) 1:500      DWG No. 1017353.2402-TT-048      REV 2		
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE				

**NOTES**  
 1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.  
 2. LEVEL DATUM: NZVD 2016.



**1 ACCESS TYPICAL SECTION**  
 021 SCALE (A1) 1:20  
 SCALE (A3) 1:40



**2 ACCESS ROAD TYPICAL SECTION**  
 021 SCALE (A1) 1:20  
 023 SCALE (A3) 1:40




www.tonkintaylor.co.nz


1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	SIDP	Jan.25	DRAWING STATUS PRELIMINARY PROJECT PHASE PRELIMINARY DESIGN	
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25		
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	TIBR	21.08.25		
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25		
REV DESCRIPTION					CAD CHK DATE		APPROVED DATE		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	ROADING SECTIONS TYPICAL SECTIONS - SHEET 1
SCALE (A1)	1:20
DWG No.	1017353.2402-TT-051
REV	4


**NOTES**  
 1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.  
 2. LEVEL DATUM: NZVD 2016.



**3 TAIHAPE ROAD TYPICAL SECTION**  
 021 SCALE (A1) 1:25  
 SCALE (A3) 1:50



**4 OHITI ROAD TYPICAL SECTION**  
 011 SCALE (A1) 1:25  
 SCALE (A3) 1:50



DESIGNED	SIDP	Jan.25	DRAWING STATUS	PRELIMINARY
DRAWN	ALPO	Jan.25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	TIBR	21.08.25	THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED	
DRAWING CHECKED	WYHU	21.08.25		
<b>NOT FOR CONSTRUCTION</b>				
APPROVED	DATE	DATE		

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	ROADING SECTIONS TYPICAL SECTIONS - SHEET 2
SCALE (A1)	1:25
DWG No.	1017353.2402-TT-052
REV	4

1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25
2	FOR REVIEW	ALPO	TIBR	18.03.25
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE


**NOTES**

- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.

**LEGEND**

100 YEAR FLOOD LEVEL

STOPBANK CREST LEVELS LIKELY TO BE LOWERED COMPARED WITH THAT INDICATED. CHANGE TO BE APPROX. 200-300mm, TO BE CONFIRMED AT DETAILED DESIGN.




**1 LONG SECTION: OHITI STOPBANK - CH 0 TO CH 350**

SCALE (A1) 1:500 (HORIZ), 1:100 (VERT)  
SCALE (A3) 1:1000 (HORIZ), 1:200 (VERT)


STOPBANK CREST LEVELS LIKELY TO BE LOWERED COMPARED WITH THAT INDICATED. CHANGE TO BE APPROX. 200-300mm, TO BE CONFIRMED AT DETAILED DESIGN.

STOPBANK CREST LEVELS LIKELY TO BE RAISED COMPARED WITH THAT INDICATED. CHANGE TO BE APPROX. 0-200mm, TO BE CONFIRMED AT DETAILED DESIGN.



**1 LONG SECTION: OHITI STOPBANK - CH 350 TO CH 700**

SCALE (A1) 1:500 (HORIZ), 1:100 (VERT)  
SCALE (A3) 1:1000 (HORIZ), 1:200 (VERT)



www.tonkintaylor.co.nz

1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS	PRELIMINARY
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	PRELIMINARY DESIGN
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25		
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25		
REV DESCRIPTION					CAD CHK DATE		APPROVED DATE		

NOT FOR CONSTRUCTION

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

CLIENT	HAWKES BAY REGIONAL COUNCIL
PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS
TITLE	STOPBANK SECTIONS OHITI STOPBANK LONG SECTION - SHEET 1
SCALE (A1)	AS SHOWN
DWG No.	1017353.2402-TT-071
REV	4

**NOTES**

- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.


**LEGEND**

100 YEAR FLOOD LEVEL


STOPBANK CREST LEVELS LIKELY TO BE RAISED COMPARED WITH THAT INDICATED. CHANGE TO BE APPROX. 0-200mm, TO BE CONFIRMED AT DETAILED DESIGN.

STOPBANK CREST LEVELS LIKELY TO BE RAISED COMPARED WITH THAT INDICATED. CHANGE TO BE APPROX. 200-300mm, TO BE CONFIRMED AT DETAILED DESIGN.


STOPBANK CREST LEVELS LIKELY TO BE RAISED COMPARED WITH THAT INDICATED. CHANGE TO BE APPROX. 300-600mm, TO BE CONFIRMED AT DETAILED DESIGN.



**1 LONG SECTION: OHITI STOPBANK - CH 700 TO CH 1050**  
 SCALE (A1) 1:500 (HORIZ), 1:100 (VERT)  
 SCALE (A3) 1:1000 (HORIZ), 1:200 (VERT)



**1 LONG SECTION: OHITI STOPBANK - CH 1050 TO CH 1400**  
 SCALE (A1) 1:500 (HORIZ), 1:100 (VERT)  
 SCALE (A3) 1:1000 (HORIZ), 1:200 (VERT)



DESIGNED	TIBR	Jan.25	DRAWING STATUS	TIBR	Jan.25
DRAWN	ALPO	Jan.25	PRELIMINARY	ALPO	Jan.25
DESIGN CHECKED	JWY	21.08.25	PROJECT PHASE	JWY	21.08.25
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN	WYHU	21.08.25
NOT FOR CONSTRUCTION			THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED		
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED
1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	
2	FOR REVIEW	ALPO	TIBR	18.03.25	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	

**CLIENT HAWKES BAY REGIONAL COUNCIL**

**PROJECT OHITI ROAD FLOOD PROTECTION STOPBANK WORKS**

**TITLE STOPBANK SECTIONS**

**OHITI STOPBANK LONG SECTION - SHEET 2**

SCALE (A1) AS SHOWN    DWG No. 1017353.2402-TT-072    REV 4




**NOTES**


1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. NORTHERN EXTENT OF OHITI STOPBANK CREST LEVELS ARE CURRENTLY DESIGNED TO THE PREVIOUS 100-YEAR ARI 2075 RCP8.5 PLUS 700mm LEVELS. UPDATE TO 2050 LEVELS WILL SHOW AN APPROXIMATELY 300mm CREST LOWERING TO THE WEST AND 300mm CREST RAISING TO THE EAST. TO BE UPDATED AT DETAILED DESIGN.
4. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.

**LEGEND**


100 YEAR FLOOD LEVEL




CHAINAGE 100




CHAINAGE 250




CHAINAGE 50



CHAINAGE 200



CHAINAGE 15



CHAINAGE 150



1:100 (A1)  
1:200 (A3)



www.tonkintaylor.co.nz

1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS	TIBR	Jan.25	PRELIMINARY
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	ALPO	Jan.25	PRELIMINARY DESIGN
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25		JWY	21.08.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25		WYHU	21.08.25	
REV DESCRIPTION					CAD CHK		DATE	APPROVED		DATE	

CLIENT	HAWKES BAY REGIONAL COUNCIL
PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS
TITLE	STOPBANK SECTIONS OHITI STOPBANK CROSS SECTION - SHEET 1
SCALE (A1)	1:100
DWG No.	1017353.2402-TT-074
REV	4


NOT FOR CONSTRUCTION THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

**NOTES**


- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016.
- NORTHERN EXTENT OF OHITI STOPBANK CREST LEVELS ARE CURRENTLY DESIGNED TO THE PREVIOUS 100-YEAR ARI 2075 RCP8.5 PLUS 700mm LEVELS. UPDATE TO 2050 LEVELS WILL SHOW AN APPROXIMATELY 300mm CREST LOWERING TO THE WEST AND 300mm CREST RAISING TO THE EAST. TO BE UPDATED AT DETAILED DESIGN.
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.

**LEGEND**


100 YEAR FLOOD LEVEL




CHAINAGE 450




CHAINAGE 600




CHAINAGE 400




CHAINAGE 550




CHAINAGE 700



CHAINAGE 300



CHAINAGE 500



CHAINAGE 650



1:100 (A1)  
1:200 (A3)



www.tonkintaylor.co.nz







<p>1 PRELIMINARY DRAFT</p> <p>2 FOR REVIEW</p> <p>3 PRELIMINARY DESIGN ISSUE</p> <p>4 REVISED PRELIMINARY DESIGN</p>	<p>ALPO MGM 24.01.25</p> <p>ALPO TIBR 18.03.25</p> <p>ALPO JWY 24.07.25</p> <p>MLE JWY 22.08.25</p>	<p>DESIGNED TIBR Jan.25</p> <p>DRAWN ALPO Jan.25</p> <p>DESIGN CHECKED JWY 21.08.25</p> <p>DRAWING CHECKED WYHU 21.08.25</p>	<p>DRAWING STATUS PRELIMINARY</p> <p>PROJECT PHASE PRELIMINARY DESIGN</p>	<p>CLIENT <b>HAWKES BAY REGIONAL COUNCIL</b></p> <p>PROJECT <b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b></p>		
		<p>NOT FOR CONSTRUCTION</p> <p>THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED</p>		<p>TITLE STOPBANK SECTIONS</p> <p>OHITI STOPBANK CROSS SECTION - SHEET 2</p>		
		<p>APPROVED</p>	<p>DATE</p>	<p>SCALE (A1) 1:100</p>	<p>DWG No. 1017353.2402-TT-075</p>	<p>REV 4</p>
		<p>REV</p>	<p>DESCRIPTION</p>	<p>CAD</p>	<p>CHK</p>	<p>DATE</p>

**NOTES**

- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016.
- NORTHERN EXTENT OF OHITI STOPBANK CREST LEVELS ARE CURRENTLY DESIGNED TO THE PREVIOUS 100-YEAR ARI 2075 RCP8.5 PLUS 700mm LEVELS. UPDATE TO 2050 LEVELS WILL SHOW AN APPROXIMATELY 300mm CREST LOWERING TO THE WEST AND 300mm CREST RAISING TO THE EAST. TO BE UPDATED AT DETAILED DESIGN.
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.

**LEGEND**

100 YEAR FLOOD LEVEL





1:100 (A1)  
1:200 (A3)




1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS	TIBR	Jan.25	PRELIMINARY
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	JWY	21.08.25	PRELIMINARY DESIGN
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25		WYHU	21.08.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25				
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE		NOT FOR CONSTRUCTION THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED			

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STOPBANK SECTIONS OHITI STOPBANK CROSS SECTION - SHEET 3
SCALE (A1)	1:100
DWG No.	1017353.2402-TT-076
REV	4


- NOTES**
- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
  - LEVEL DATUM: NZVD 2016.
  - NORTHERN EXTENT OF OHITI STOPBANK CREST LEVELS ARE CURRENTLY DESIGNED TO THE PREVIOUS 100-YEAR ARI 2075 RCP8.5 PLUS 700mm LEVELS. UPDATE TO 2050 LEVELS WILL SHOW AN APPROXIMATELY 300mm CREST LOWERING TO THE WEST AND 300mm CREST RAISING TO THE EAST. TO BE UPDATED AT DETAILED DESIGN.
  - FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.




CHAINAGE 1150




CHAINAGE 1100




CHAINAGE 1050




CHAINAGE 1300




CHAINAGE 1250




CHAINAGE 1200



CHAINAGE 1450



CHAINAGE 1400



CHAINAGE 1350



1:100 (A1)  
1:200 (A3)



1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS	TIBR	Jan.25	PRELIMINARY
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	ALPO	Jan.25	PRELIMINARY DESIGN
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25		JWY	21.08.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25		WYHU	21.08.25	
REV DESCRIPTION		CAD	CHK	DATE	APPROVED		DATE	NOT FOR CONSTRUCTION			

CLIENT	HAWKES BAY REGIONAL COUNCIL
PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS
TITLE	STOPBANK SECTIONS OHITI STOPBANK CROSS SECTION - SHEET 4
SCALE (A1)	1:100
DWG No.	1017353.2402-TT-077
REV	4







THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

**NOTES**

1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. NORTHERN EXTENT OF OHITI STOPBANK CREST LEVELS ARE CURRENTLY DESIGNED TO THE PREVIOUS 100-YEAR ARI 2075 RCP8.5 PLUS 700mm LEVELS. UPDATE TO 2050 LEVELS WILL SHOW AN APPROXIMATELY 300mm CREST LOWERING TO THE WEST AND 300mm CREST RAISING TO THE EAST. TO BE UPDATED AT DETAILED DESIGN.
4. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.

**LEGEND**

100 YEAR FLOOD LEVEL



1:100 (A1)  
1:200 (A3)



www.tonkintaylor.co.nz

1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS	TIBR	Jan.25	PRELIMINARY
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	JWY	21.08.25	PRELIMINARY DESIGN
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25		WYHU	21.08.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25				
REV DESCRIPTION		CAD	CHK	DATE	APPROVED		DATE	NOT FOR CONSTRUCTION			
								THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED			


CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STOPBANK SECTIONS OHITI STOPBANK CROSS SECTION - SHEET 5
SCALE (A1)	1:100
DWG No.	1017353.2402-TT-078
REV	4

**NOTES**



- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016.
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.

**LEGEND**


100 YEAR FLOOD LEVEL



**1 LONG SECTION: CHESTERHOPE UPPER STOPBANK - CH 0 TO CH 350**  
 SCALE (A1) 1:500 (HORIZ), 1:100 (VERT)  
 SCALE (A3) 1:1000 (HORIZ), 1:200 (VERT)



**1 LONG SECTION: CHESTERHOPE UPPER STOPBANK - CH 350 TO CH 393**  
 SCALE (A1) 1:500 (HORIZ), 1:100 (VERT)  
 SCALE (A3) 1:1000 (HORIZ), 1:200 (VERT)



REV	DESCRIPTION	CAD	CHK	DATE	DESIGNED	TIBR	DATE	DRAWING STATUS
1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	TIBR	Jan.25	PRELIMINARY	
2	FOR REVIEW	ALPO	TIBR	18.03.25	ALPO	Jan.25	PRELIMINARY	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	JWY	21.08.25	PRELIMINARY DESIGN	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	WYHU	21.08.25	PRELIMINARY DESIGN	

**NOT FOR CONSTRUCTION** THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED


<b>CLIENT</b>	<b>HAWKES BAY REGIONAL COUNCIL</b>
<b>PROJECT</b>	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
<b>TITLE</b>	<b>STOPBANK SECTIONS CHESTERHOPE UPPER STOPBANK LONG SECTION</b>
<b>SCALE (A1)</b>	<b>AS SHOWN</b>
<b>DWG No.</b>	<b>1017353.2402-TT-081</b>
<b>REV</b>	<b>4</b>

**NOTES**

- ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
- LEVEL DATUM: NZVD 2016.
- FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.


**LEGEND**

100 YEAR FLOOD LEVEL




DATUM (mRL) 26.0	
DESIGN LEVEL	27.92 27.92 28.06 29.17 29.73 29.73 29.73 29.73 29.17 28.71 28.71 28.71
EXISTING LEVEL	27.92 27.87 28.24 28.30 28.35 28.35 28.28 28.28 28.61 28.71 28.71 28.71
OFFSET	-4.25 -4.00 -2.00 -1.00 0.00 0.00 1.00 2.00 2.83 2.83 2.83

CHAINAGE 100




DATUM (mRL) 26.0	
DESIGN LEVEL	30.47 30.33 30.33 30.33 30.33 30.49
EXISTING LEVEL	27.72 27.72 27.72 27.72 27.72 27.73
OFFSET	-2.41 -2.00 -2.00 0.00 2.00 2.47

CHAINAGE 50




DATUM (mRL) 26.0	
DESIGN LEVEL	28.53 28.73 28.73 28.73 28.73 27.95
EXISTING LEVEL	28.53 28.66 28.66 28.70 28.34 28.34 27.95
OFFSET	-2.51 -2.00 -2.00 0.00 0.00 2.00 2.00 3.95

CHAINAGE 200



DATUM (mRL) 26.0	
DESIGN LEVEL	28.34 28.36 28.76 29.16 29.56 29.56 30.36 30.36 30.36 29.96 29.56 29.16 28.76 28.36 27.96 27.72
EXISTING LEVEL	28.34 28.31 28.00 27.82 28.00 27.95 27.78 27.78 28.01 27.74 27.74 27.63 27.56 27.50 27.61 27.47 27.76 27.72
OFFSET	-12.06 -12.00 -10.00 -8.00 -6.00 -4.00 -2.00 -2.00 0.00 2.00 2.00 4.00 6.00 8.00 10.00 12.00 14.00 15.16

CHAINAGE 15



DATUM (mRL) 27.0	
DESIGN LEVEL	28.71 28.78 28.78 28.78 28.75 28.75
EXISTING LEVEL	28.71 28.71 28.74 28.76 28.75 28.75
OFFSET	-1.19 -1.00 0.00 1.00 1.07 1.07

CHAINAGE 150



1:100 (A1)  
1:200 (A3)



www.tonkintaylor.co.nz





1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS	PRELIMINARY	CLIENT	HAWKES BAY REGIONAL COUNCIL			
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	PRELIMINARY DESIGN	PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS			
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25	TITLE	STOPBANK SECTIONS					
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25		CHESTERHOPE UPPER STOPBANK CROSS SECTION - SHEET 1					
REV	DESCRIPTION	CAD	CHK	DATE	NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED		SCALE (A1)	1:100	DWG No.	1017353.2402-TT-082	REV	4

**NOTES**

1. ALL DIMENSIONS IN METRES UNLESS STATED OTHERWISE.
2. LEVEL DATUM: NZVD 2016.
3. FINAL LEVELS TO BE REFINED AT DETAILED DESIGN TO ACCOMMODATE FINAL FLOOD MODELLING, LOCAL TOPOGRAPHY AND DESIGN REQUIREMENTS.

**LEGEND**

100 YEAR FLOOD LEVEL



1:100 (A1)  
1:200 (A3)




www.tonkintaylor.co.nz


1	PRELIMINARY DRAFT	ALPO	MGM	24.01.25	DESIGNED	TIBR	Jan.25	DRAWING STATUS	TIBR	Jan.25	PRELIMINARY
2	FOR REVIEW	ALPO	TIBR	18.03.25	DRAWN	ALPO	Jan.25	PROJECT PHASE	ALPO	Jan.25	PRELIMINARY DESIGN
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	DESIGN CHECKED	JWY	21.08.25		ALPO	21.08.25	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	DRAWING CHECKED	WYHU	21.08.25		MLE	21.08.25	
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE		NOT FOR CONSTRUCTION			

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED

CLIENT	HAWKES BAY REGIONAL COUNCIL
PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS
TITLE	STOPBANK SECTIONS CHESTERHOPE UPPER STOPBANK CROSS SECTION - SHEET 2
SCALE (A1)	1:100
DWG No.	1017353.2402-TT-083
REV	4



**1 1 EMBANKMENT DETAIL: CHESTERHOPE UPPER STOPBANK TYPICAL SOUTHERN SECTION**  
 SCALE (A1) 1:50  
 SCALE (A3) 1:100



**2 2 EMBANKMENT DETAIL: CHESTERHOPE UPPER STOPBANK TYPICAL WESTERN SECTION**  
 SCALE (A1) 1:50  
 SCALE (A3) 1:100

**NOTES**

- ALL DIMENSIONS IN MILLIMETRES UNLESS NOTED OTHERWISE.
- TOPO SURVEY SUPPLIED BY THE SURVEYING COMPANY, REF "232589-Topo-3D.dwg" DATED 28 NOV 2023.

**LEGEND**

- EXISTING GROUND LEVEL
- 100 YEAR FLOOD LEVEL
- XXXXX PROPOSED STOPBANK FILL
- TOPSOIL AND GRASS
- EXISTING SANDY/SILT FILL
- EXISTING SANDY GRAVEL
- ECC3 TURF MATTING




www.tonkintaylor.co.nz

DESIGNED	PELE	April.25	DRAWING STATUS	PRELIMINARY
DRAWN	STLP	April.25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	JWY	21.08.25		
DRAWING CHECKED	WYHU	21.08.25		
NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED		
APPROVED	DATE			

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STOPBANK SECTIONS TYPICAL CROSS SECTIONS - CHESTERHOPE
SCALE (A1)	1:50
DWG No.	1017353.2402-TT-091
REV	2

1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE



**1 EMBANKMENT DETAIL: OHITI STOPBANK TYPICAL SECTION**  
 011 SCALE (A1) 1:50  
 SCALE (A3) 1:100

**NOTES**

- ALL DIMENSIONS IN MILLIMETRES UNLESS NOTED OTHERWISE.
- TOPO SURVEY SUPPLIED BY THE SURVEYING COMPANY, REF "232589-Topo-3D.dwg" DATED 28 NOV 2023.

**LEGEND**

- EXISTING GROUND LEVEL
- 100 YEAR FLOOD LEVEL
- XXXXX PROPOSED STOPBANK FILL
- TOPSOIL AND GRASS




www.tonkintaylor.co.nz


DESIGNED	REKI	Jun.25	DRAWING STATUS	PRELIMINARY		
DRAWN	ALPO	Jun..25	PROJECT PHASE	PRELIMINARY DESIGN		
DESIGN CHECKED	JWY	21.08.25				
DRAWING CHECKED	WYHU	21.08.25				
NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED				
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25		
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25		

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STOPBANK SECTIONS TYPICAL SECTION - OHITI
SCALE (A1)	1:50
DWG No.	1017353.2402-TT-092
REV	2

- NOTES**
1. COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
  2. AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
  3. PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
  4. EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".



**OHITI ROAD PLAN - CH 160 TO CH 240**  
 SCALE (A1) 1:250  
 SCALE (A3) 1:500



**OHITI ROAD PLAN - CH 0 TO CH 160**  
 SCALE (A1) 1:250  
 SCALE (A3) 1:500




www.tonkintaylor.co.nz


DESIGNED	SIDP	Jul.25	DRAWING STATUS			
DRAWN	ALPO	Jul.25	PRELIMINARY			
DESIGN CHECKED	TIBR	21.08.25	PROJECT PHASE			
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN			
<b>NOT FOR CONSTRUCTION</b>			THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED			
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25		
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25		

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	ROADING AND TRANSPORT SIGNAGE AND ROAD MARKINGS PLAN - SHEET 1
SCALE (A1)	1:250
DWG No.	1017353.2402-TT-541
REV	2

- NOTES**
- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
  - AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
  - PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
  - EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".



**TAIHAPE ROAD PLAN - CH 1220 TO CH 1380**  
 SCALE (A1) 1:250  
 SCALE (A3) 1:500




**TAIHAPE ROAD PLAN - CH 1380 TO CH 1560**  
 SCALE (A1) 1:250  
 SCALE (A3) 1:500



DESIGNED	SIDP	Jul.25	DRAWING STATUS	PRELIMINARY
DRAWN	ALPO	Jul.25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	TIBR	21.08.25	THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED	
DRAWING CHECKED	WYHU	21.08.25		
<b>NOT FOR CONSTRUCTION</b>				
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE
		APPROVED		DATE

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD AND TAIHAPE ROAD STOPBANK</b>
TITLE	ROADING AND TRANSPORT SIGNAGE AND ROAD MARKINGS PLAN - SHEET 2
SCALE (A1)	1:250
DWG No.	1017353.2402-TT-542
REV	2



**TAIHAPE ROAD PLAN - CH 1560 TO CH 1710**

SCALE (A1) 1:250  
SCALE (A3) 1:500



**TAIHAPE ROAD PLAN - CH 1710 TO CH 1900**

SCALE (A1) 1:250  
SCALE (A3) 1:500

- NOTES**
- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
  - AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
  - PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
  - EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omahu Filtered.ias".



www.tonkintaylor.co.nz

DESIGNED	SIDP	Jul.25	DRAWING STATUS			
DRAWN	ALPO	Jul.25	PRELIMINARY			
DESIGN CHECKED	TIBR	21.08.25	PROJECT PHASE			
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN			
<b>NOT FOR CONSTRUCTION</b>			THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED			
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25		
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25		


<b>CLIENT</b>	<b>HAWKES BAY REGIONAL COUNCIL</b>
<b>PROJECT</b>	<b>OHITI ROAD AND TAIHAPE ROAD STOPBANK</b>
<b>TITLE</b>	<b>ROADING AND TRANSPORT SIGNAGE AND ROAD MARKINGS PLAN - SHEET 3</b>
<b>SCALE (A1)</b>	1:250
<b>DWG No.</b>	1017353.2402-TT-543
<b>REV</b>	2

**NOTES**


- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
- PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.

**LEGEND**


- PROPERTY BOUNDARY
- PROPOSED STOPBANK
- PROPOSED ROAD EXTENT
- 500mm ADDITIONAL CLEARANCE
- VEHICLE BODY ENVELOPE
- WHEEL PATH




**PLAN 01**  
SCALE (A1) 1:250  
SCALE (A3) 1:500




**PLAN 02**  
SCALE (A1) 1:250  
SCALE (A3) 1:500



AT - 95TH - CAR  
OVERALL LENGTH 5.060m  
OVERALL WIDTH 1.923m  
OVERALL BODY HEIGHT 1.784m  
MIN BODY GROUND CLEARANCE 0.231m  
MAX TRACK WIDTH 1.888m  
LOCK-TO-LOCK TIME 4.00s  
CURB TO CURB TURNING RADIUS 6.450m



AT - TRUCK - 8.3m TRUCK  
OVERALL LENGTH 8.300m  
OVERALL WIDTH 2.500m  
OVERALL BODY HEIGHT 3.471m  
MIN BODY GROUND CLEARANCE 0.373m  
TRACK WIDTH 2.500m  
LOCK-TO-LOCK TIME 6.00s  
MAX STEERING ANGLE (VIRTUAL) 40.20°



AT - TRUCK - HPMV - 19.45m SEMI-TRAILER (REAR STEER)  
OVERALL LENGTH 19.380m  
OVERALL WIDTH 2.500m  
OVERALL BODY HEIGHT 4.386m  
MIN BODY GROUND CLEARANCE 0.311m  
TRACK WIDTH 2.500m  
LOCK-TO-LOCK TIME 6.00s  
WALL TO WALL TURNING RADIUS 12.500m



1:250 (A1)  
1:500 (A3)




www.tonkintaylor.co.nz

REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE
1	PRELIMINARY DRAFT (AS DRG 1017353.2402-TT-025)	ALPO	MGM	24.01.25		
2	PRELIMINARY DESIGN (AS DRG 1017353.2402-TT-025)	ALPO	TIBR	18.03.25		
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25		
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25		

DESIGNED	SIDP	Jan.25	DRAWING STATUS
DRAWN	ALPO	Jan.25	PRELIMINARY
DESIGN CHECKED	TIBR	21.08.25	PROJECT PHASE
DRAWING CHECKED	WYHU	21.08.25	PRELIMINARY DESIGN
NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED	
APPROVED	DATE		


CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	ROADING AND TRANSPORT <b>TAIHAPE ROAD - VEHICLE TRACKING PLAN</b>
SCALE (A1)	1:250
DWG No.	1017353.2402-TT-551
REV	4



ID	CATEGORY	LOCATION	DESIGN SPEED	85th PERCENTILE SPEED	REACTION TIME	FRICTION COEFT.	ROAD LONGITUDINAL GRADIENT	REQUIRED SSD	SSD ACHIEVED?
			(km/h)	(km/h)	(s)		(%)	(m)	(Y/N)
1	SSD	TAIHAPE ROAD WESTBOUND	110	93.5	2	0.29	-0.8	233.1	Y
2	SSD	TAIHAPE ROAD EASTBOUND	110	93.5	2	0.29	-1.4	233.7	Y

- NOTES**
- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
  - PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.

- LEGEND**
- PROPERTY BOUNDARY (Red dashed line)
  - PROPOSED STOPBANK (Black line with triangles)
  - PROPOSED ROAD EXTENT (Grey shaded area)
  - PROPOSED ROAD CENTERLINE (Yellow line)
  - PROPOSED BUS STOP (Blue dashed line)
  - VIEWSHAFT (Green dashed line)



REV	DESCRIPTION	CAD	CHK	DATE	DESIGNED	SIDP	DATE	DRAWING STATUS
1	PRELIMINARY DRAFT (AS DRG 1017353.2402-TT-026)	ALPO	MGM	24.01.25	SIDP	Jan.25	PRELIMINARY	
2	PRELIMINARY DESIGN (AS DRG 1017353.2402-TT-026)	ALPO	TIBR	18.03.25	ALPO	Jan.25	PRELIMINARY	
3	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	TIBR	21.08.25	PROJECT PHASE	
4	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	WYHU	21.08.25	PRELIMINARY DESIGN	

**NOT FOR CONSTRUCTION**

APPROVED DATE

**CLIENT HAWKES BAY REGIONAL COUNCIL**

**PROJECT OHITI ROAD FLOOD PROTECTION STOPBANK WORKS**

**TITLE ROADING AND TRANSPORT**

**TAIHAPE ROAD - SIGHT DISTANCE PLAN**

SCALE (A1) 1:500      DWG No. 1017353.2402-TT-571      REV 4

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED




**NOTES**

- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
- AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
- PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
- EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".

**LEGEND**


- PROPERTY BOUNDARY
- EXISTING MAJOR CONTOUR (5m INTERVAL)
- EXISTING MINOR CONTOUR (1m INTERVAL)
- PROPOSED MAJOR CONTOUR (1m INTERVAL)
- PROPOSED MINOR CONTOUR (0.5m INTERVAL)
- PROPOSED STOPBANK
- PROPOSED ROAD EXTENT
- PROPOSED ROAD MARKING - 100mm WIDE WHITE CONTINUOUS LINE
- PROPOSED ROAD MARKING - 100mm WIDE WHITE CENTERLINE (3m STRIPE, 7m GAP)
- EXISTING ROAD MARKING - 100mm WIDE WHITE CENTERLINE (3m STRIPE, 7m GAP)
- PROPOSED CULVERT



DESIGNED	THWA	Jul,25	DRAWING STATUS	PRELIMINARY
DRAWN	ALPO	Jul,25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	JWY	21.08.25		
DRAWING CHECKED	WYHU	21.08.25		
NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED		
APPROVED	DATE			

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STORMWATER CULVERT LAYOUT PLAN - OHITI ROAD
SCALE (A1)	1:1250
DWG No.	1017353.2402-TT-611
REV	2


1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE



NOTES	
1.	COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
2.	AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
3.	PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
4.	EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.ias".

LEGEND	
	PROPERTY BOUNDARY
	EXISTING MAJOR CONTOUR (5m INTERVAL)
	EXISTING MINOR CONTOUR (1m INTERVAL)
	PROPOSED MAJOR CONTOUR (1m INTERVAL)
	PROPOSED MINOR CONTOUR (0.5m INTERVAL)
	PROPOSED STOPBANK
	PROPOSED CULVERT
	PROPOSED SWALE




**CULVERT LAYOUT PLAN - TAIHAPE ROAD**  
 SCALE (A1) 1:1000  
 SCALE (A3) 1:2000




REV	DESCRIPTION	CAD	CHK	DATE	DESIGNED	THWA	DATE	DRAWING STATUS
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25	THWA	Jul.25		DRAWING STATUS
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25	ALPO	Jul.25		PRELIMINARY
					JWY	21.08.25		PROJECT PHASE
					WYHU	21.08.25		PRELIMINARY DESIGN
					NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED	
					APPROVED	DATE		

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STORMWATER CULVERT LAYOUT PLAN - TAIHAPE ROAD
SCALE (A1)	AS SHOWN
DWG No.	1017353.2402-TT-621
REV	2



**CULVERT LAYOUT PLAN - SMITH PROPERTY**

SCALE (A1) 1:500  
SCALE (A3) 1:1000



**1 TYPICAL CHANNEL CROSS SECTION**


SCALE (A1) 1:250  
SCALE (A3) 500

**NOTES**

- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
- AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
- PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
- EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.ias".

**LEGEND**


- PROPERTY BOUNDARY
- EXISTING MAJOR CONTOUR (5m INTERVAL)
- EXISTING MINOR CONTOUR (1m INTERVAL)
- PROPOSED MAJOR CONTOUR (1m INTERVAL)
- PROPOSED MINOR CONTOUR (0.5m INTERVAL)
- PROPOSED STOPBANK
- CHANNEL
- PROPOSED CULVERT
- 100 YEAR FLOOD LEVEL




www.tonkintaylor.co.nz

DESIGNED	STLP	Jul,25	DRAWING STATUS	PRELIMINARY		
DRAWN	ALPO	Jul,25	PROJECT PHASE	PRELIMINARY DESIGN		
DESIGN CHECKED	JWY	21.08.25				
DRAWING CHECKED	WYHU	21.08.25				
<b>NOT FOR CONSTRUCTION</b>						
THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED						
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25		
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25		


CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STORMWATER CULVERT LAYOUT PLAN - SMITH PROPERTY
SCALE (A1)	AS SHOWN
DWG No.	1017353.2402-TT-631
REV	2




**1 LINE SW 01**  
611 SCALE (A1) 1:500 (H), 1:100 (V)  
SCALE (A3) 1:1000 (H), 1:2000 (V)



**2 LINE SW 02**  
611 SCALE (A1) 1:500 (H), 1:100 (V)  
SCALE (A3) 1:1000 (H), 1:2000 (V)



**3 LINE SW 03**  
611 SCALE (A1) 1:500 (H), 1:100 (V)  
SCALE (A3) 1:1000 (H), 1:2000 (V)




www.tonkintaylor.co.nz

DESIGNED	STLP	Jul,25	DRAWING STATUS	PRELIMINARY
DRAWN	ALPO	Jul,25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	JWY	21.08.25		
DRAWING CHECKED	WYHU	21.08.25		
NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED		
APPROVED	DATE			

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STORMWATER CULVERT - LONG SECTIONS
SCALE (A1)	1:500
DWG No.	1017353.2402-TT-651
REV	2


REV	DESCRIPTION	CAD	CHK	DATE
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25

**HOLD:**  
SCRUFFY DOME MANHOLE LOCATION AND FINISHED GROUND LEVEL TO BE CONFIRMED AT DETAILED DESIGN




DATUM (mRL) 27		RCRRJ Class 2 DN750 GRADE: 1 in 200 LENGTH: 16.34m									
PIPE INFO											
DESIGN LEVEL	31.09										
EXISTING LEVEL	31.09										
CHAINAGE (m)	-14.12										
PIPE INVERT LEVEL	29.57										
DEPTH TO PIPE INVERT	1.52										

**1 CULVERT / SWALE LONG SECTION - CH -14.1 TO CH 170**  
631 SCALE (A1) 1:250 (H), 1:50 (V)  
SCALE (A3) 1:500 (H), 1:100 (V)



DATUM (mRL) 25											
DESIGN LEVEL	28.63										
EXISTING LEVEL	30.34										
CHAINAGE (m)	175.00										

**1 CULVERT / SWALE LONG SECTION - CH 170 TO CH 295**  
631 SCALE (A1) 1:250 (H), 1:50 (V)  
SCALE (A3) 1:500 (H), 1:100 (V)




www.tonkintaylor.co.nz

DESIGNED	STLP	Jul,25	DRAWING STATUS	PRELIMINARY
DRAWN	ALPO	Jul,25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	JWY	21.08.25		
DRAWING CHECKED	WYHU	21.08.25		
NOT FOR CONSTRUCTION		THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED		
APPROVED	DATE			

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STORMWATER SMITH PROPERTY CULVERT / SWALE LONG SECTION
SCALE (A1)	1:500
DWG No.	1017353.2402-TT-661
REV	2

1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE



**1 TAIHAPE ROAD ACCESS TRACK CROSS SECTION (CHAINAGE 960)**  
 621 SCALE (A1) 1:500  
 SCALE (A3) 1:1000



www.tonkintaylor.co.nz

DESIGNED	STLP	Jul,25	DRAWING STATUS	PRELIMINARY
DRAWN	ALPO	Jul,25	PROJECT PHASE	PRELIMINARY DESIGN
DESIGN CHECKED	JWY	21.08.25		
DRAWING CHECKED	WYHU	21.08.25		
<b>NOT FOR CONSTRUCTION</b>		<small>THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED</small>		
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE


CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	STORMWATER TAIHAPE ROAD ACCESS TRACK SECTION
SCALE (A1)	1:500
DWG No.	1017353.2402-TT-671
REV	2

**NOTES**

- COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
- AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
- PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
- EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".
- EXISTING SERVICES SOURCED BY T+T FROM TRANSPOWER LTD, HASTINGS DISTRICT COUNCIL AND HAWKES BAY REGIONAL COUNCIL OPEN GIS DATA ON 10/07/2025.

**LEGEND**

- PROPERTY BOUNDARY
- EXISTING MAJOR CONTOUR (10m INTERVAL)
- EXISTING MINOR CONTOUR (5m INTERVAL)
- PROPOSED STOPBANK
- OH/HV EXISTING UNISON HIGH VOLTAGE OVERHEAD LINE
- OH/LV EXISTING UNISON LOW VOLTAGE OVERHEAD LINE
- OH/HV EXISTING TRANSPOWER TRANSLINE
- EXISTING HBRC DRAINS AND WELLS



www.tonkintaylor.co.nz

DESIGNED	STLP	Jul.25	DRAWING STATUS	PRELIMINARY		
DRAWN	ALPO	Jul.25	PROJECT PHASE	PRELIMINARY DESIGN		
DESIGN CHECKED	JWY	21.08.25	NOT FOR CONSTRUCTION THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED			
DRAWING CHECKED	WYHU	21.08.25				
1	ALPO	JWY	24.07.25			
2	MLE	JWY	22.08.25			
REV	DESCRIPTION	CAD	CHK	DATE	APPROVED	DATE



CLIENT	HAWKES BAY REGIONAL COUNCIL
PROJECT	OHITI ROAD FLOOD PROTECTION STOPBANK WORKS
TITLE	UTILITIES UTILITIES PLAN - OHITI ROAD
SCALE (A1)	1:1250
DWG No.	1017353.2402-TT-811
REV	2

**NOTES**

1. COORDINATE DATUM: NZGD2000, NEW ZEALAND TRANSVERSE MERCATOR (NZTM2000).
2. AERIAL PHOTO SOURCED FROM LAND INFORMATION NEW ZEALAND DATA (CROWN COPYRIGHT RESERVED).
3. PROPERTY BOUNDARIES SUPPLIED BY The Surveying Company Limited, REF "243082-TP-01.DWG" DATED 29/02/2024.
4. EXISTING CONTOUR DERIVED FROM 20240301 UAV DATA, REF "HBRC Omaha Filtered.las".
5. EXISTING SERVICES SOURCED BY T+T FROM TRANSPOWER LTD, HASTINGS DISTRICT COUNCIL AND HAWKES BAY REGIONAL COUNCIL OPEN GIS DATA ON 10/07/2025.

**LEGEND**

- — — — — PROPERTY BOUNDARY
- 30 — — — — — EXISTING MAJOR CONTOUR (10m INTERVAL)
- — — — — EXISTING MINOR CONTOUR (5m INTERVAL)
- ▬▬▬▬▬▬▬ PROPOSED STOPBANK
- ▬▬▬▬▬▬▬ PROPOSED ROAD EXTENT
- ▬▬▬▬▬▬▬ SHARED DRIVEWAY
- OHHV — — — — — EXISTING UNISON HIGH VOLTAGE OVERHEAD LINE
- OHLV — — — — — EXISTING UNISON LOW VOLTAGE OVERHEAD LINE
- OHTV — — — — — EXISTING TRANSPOWER TRANSLINE
- — — — — EXISTING HBRC DRAINS AND WELLS
- — — — — EXISTING UG NETWORK
- DISTRIBUTION PILLAR
- CHORUS POLE



www.tonkintaylor.co.nz

DESIGNED	STLP	Jul.25		
DRAWN	ALPO	Juk.25		
DESIGN CHECKED	JWY	21.08.25		
DRAWING CHECKED	WYHU	21.08.25		
1	PRELIMINARY DESIGN ISSUE	ALPO	JWY	24.07.25
2	REVISED PRELIMINARY DESIGN	MLE	JWY	22.08.25
REV	DESCRIPTION	CAD	CHK	DATE

DRAWING STATUS	PRELIMINARY
PROJECT PHASE	PRELIMINARY DESIGN
<b>NOT FOR CONSTRUCTION</b>	
<small>THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION PURPOSES UNLESS SIGNED AS APPROVED</small>	
APPROVED	DATE

CLIENT	<b>HAWKES BAY REGIONAL COUNCIL</b>
PROJECT	<b>OHITI ROAD FLOOD PROTECTION STOPBANK WORKS</b>
TITLE	UTILITIES UTILITIES PLAN - TAIHAPE ROAD
SCALE (A1)	1:1000
DWG No.	1017353.2402-TT-821
REV	2

## **Appendix B      Consent conditions**

---

**Table Appendix B.1: Consent condition review summary**

Number	Standardised conditions and proposed changes	Corresponding actions taken/design intent
12	<p>Earthworks principles</p> <ol style="list-style-type: none"> <li>1 The consent holder must carry out all works in a manner that—               <ol style="list-style-type: none"> <li>a) minimises the volume, area, and duration of the proposed earthworks required through methodologies, including the design of batter slopes, appropriate to expected soil types and geology; and</li> <li>b) maximises the effectiveness of erosion and sediment control measures associated with earthworks by minimising potential for sediment generation and sediment yield; and</li> <li>c) avoids if practicable, or minimises so far as practicable, adverse effects on freshwater and marine water environments within or beyond the works boundary, with particular regard to reducing opportunities for the works to generate sediment; and</li> <li>d) avoids if practicable, or minimises so far as practicable, adverse effects on outstanding natural features, outstanding natural landscapes, and areas of outstanding natural character (as specified in a regional plan or policy statement for the relevant area); and</li> <li>e) avoids if practicable, or minimises so far as practicable, adverse effects on culturally significant land; and</li> <li>f) stabilises disturbed land as soon as reasonably practicable in accordance with an ESCP.</li> </ol> </li> <li>2 The consent holder must, as far as practicable, ensure that earthworks are carried out in accordance with the ecology principles.</li> </ol>	<p>The proposed design includes modest batter slopes (1V:2.5H to 1V:3H), to help minimise effects of scour in potential overtopping events. The footprint of the stopbank is largely dictated by the flood level relative to existing ground levels and existing easements or property considerations. Steeper sections of batters will be stabilised with specialist matting and all stopbank sections will be topsoiled to mitigate against erosion.</p> <p>The extent of the stopbank has largely been dictated by minimising effects on adjacent landowners and agreeing a land acquisition strategy. This has however resulted in a need to reduce stopbank footprints where possible and work within existing easements.</p> <p>We understand that HBRC have engaged others to review cultural and natural character impacts.</p> <p>Further details on how the earthworks and ecological principles will be implemented will be detailed in the CEMP and ESCP.</p>
14	<p><b>Erosion and sediment control plan</b></p> <ol style="list-style-type: none"> <li>3 The consent holder must prepare 1 or more erosion and sediment control plans for the works to identify how the earthworks principles will be applied.</li> <li>4 The consent holder must engage a suitably qualified and experienced person to prepare an ESCP.</li> <li>5 An ESCP must specify the following matters:           <p><i>General</i></p> <ol style="list-style-type: none"> <li>a) how the works will be carried out in accordance with the ecology principles:</li> <li>b) structural and non-structural erosion and sediment control measures (including chemical treatment where necessary) to be in place before and during all construction works, including earthworks, coastal works, and works within watercourses:</li> <li>c) key environmental risks, particularly in relation to topography, soil type and form, and the receiving environment, including proximity to any sensitive receivers (for example, watercourses):</li> <li>d) procedures for ensuring advance warning of a rainfall event:</li> <li>e) procedures for decommissioning the erosion and sediment control measures:</li> <li>f) procedures for determining the staging and sequencing of earthworks:</li> <li>g) methods adopted, for the purpose of reducing sediment loss and erosion, to stabilise—               <ol style="list-style-type: none"> <li>i. any excavated area; and</li> <li>ii. (any watercourse bed; and</li> <li>iii. (any banks of a watercourse that have been disturbed by the works:</li> </ol> </li> <li>h) details of maintenance, including actions and frequency:</li> <li>i) supporting information about the size of erosion and sediment control devices:</li> <li>j) methods for amending and updating the ESCP as required:</li> </ol> <p><i>Erosion and Sediment Control Manager and staff</i></p> <ol style="list-style-type: none"> <li>a) the name and contact details of the Erosion and Sediment Control Manager:</li> <li>b) the names and contact details of other staff appointed to assist with the management of erosion and sediment control (see clause 13(4) of this schedule):</li> </ol> <p><i>Incident management</i></p> <ol style="list-style-type: none"> <li>a) the process for detecting, investigating, and recording, and for notifying the consent authority of, incidents that result in the discharge of contaminants or material into any watercourse due to the structural failure of any erosion and sediment control measures:</li> </ol> <p><i>Monitoring</i></p> <ol style="list-style-type: none"> <li>a) procedures for—               <ol style="list-style-type: none"> <li>i. ongoing visual inspection, and where necessary quantitative monitoring, of all erosion and sediment control measures; and</li> <li>ii. detailed analysis of trends in erosion and sediment control effectiveness and performance; and</li> <li>iii. amendments to any ESCP resulting from the activities under subparagraphs (i) and (ii):</li> </ol> </li> </ol> <p><i>Reporting to consent authority</i></p> <ol style="list-style-type: none"> <li>a) details (including timing) of reporting to the consent authority on the outcomes of, and compliance with, the ESCP.</li> </ol> </li> <li>6 The level of detail and the measures proposed in the ESCP must correspond to the nature and scale of the relevant works.</li> <li>7 The ESCP must include a site-specific risk-based approach that allows for the Erosion and Sediment Control Manager to determine the level of information and design that must be provided for specific activities.</li> <li>8 For works in or adjacent to a watercourse, an ESCP must, so far as is practicable, be consistent with the HBRC Erosion and Sediment Guidelines.</li> <li>9 The consent holder must implement an ESCP for the duration of the flood protection works.</li> <li>10 The consent holder must, for the duration of the construction works,—           <ol style="list-style-type: none"> <li>a) keep an ESCP; and</li> <li>b) make it readily available to the consent authority.</li> </ol> </li> </ol>	<p>ESCP Plan is to be developed by the contractor based on the proposed design and construction methodology.</p> <p>The ESCP will need to detail the following matters.</p> <ul style="list-style-type: none"> <li>• Erosion and sediment controls associated with stockpiling and stockpile management. Such matters could include options to mitigate dust and runoff (i.e. covering or stabilising of stockpiles).</li> <li>• Management of the borrow site and treatment of any water to be discharged from the borrow pit prior to stabilising.</li> <li>• Stabilising access roads for truck traffic coming into the site. It is likely that haul roads will need to be stabilised with gravel to mitigate dust.</li> <li>• Keep clean water clear of the construction site by diverting it around the perimeter of the site, including runoff down from stopbank crests. This may need to be staged to manage runoff while the stopbank is built. For example, culverts and swales through the stopbank site may need to be constructed early in the programme to provide conveyance of clean water through the site.</li> <li>• Any stormwater entering the stopbank earthworks site up to design level events will be treated as dirty water and will be diverted to a treatment device or banded off to avoid discharge to watercourses.</li> <li>• Treated water will most likely discharge to ground via soakage (as the underlying soils are very permeable), any runoff in larger events will be discharged (once treated) into appropriate devices as specified by the contractor.</li> <li>• Specific mention will need to be made of management of erosion and sediment controls associated with works adjacent to the Okawa stream.</li> </ul>

Number	Standardised conditions and proposed changes	Corresponding actions taken/design intent
16	<p><b>Dust Management</b></p> <p>The consent holder must, as far as practicable, ensure that dust arising from construction works (including earthworks and related activities) does not spread beyond the boundary of the work sites.</p>	<p>Dust management details will be confirmed by the Contractor but should generally include:</p> <ul style="list-style-type: none"> <li>• Dust controls should be developed in accordance with the Ministry for the Environment Good Practice Guide for Assessing and Managing the Environmental Effects of Dust Emissions (MfE, 2016).</li> <li>• A watercart for dust control should be used to wet excavation works or work areas where necessary.</li> <li>• Site access roads are to be stabilised with aggregate.</li> <li>• Daily forecast wind speed, wind direction and soil conditions will be reviewed before commencing activities with high dust generation potential. Works should be monitored during strong winds and ceased temporarily if dust becomes a nuisance.</li> <li>• The area of surfaces covered with fine materials will be minimised and exposed surfaces will be temporarily tracked rolled to seal off or stabilised with geofabric wherever practicable.</li> <li>• If required, dust shielding (such as shelter cloth on fences) could be installed where practicable.</li> </ul>
17	<p><b>Works on contaminated land</b></p> <ol style="list-style-type: none"> <li>1 This clause applies if the consent holder undertakes earthworks or any other soil disturbance on contaminated land.</li> <li>2 The consent holder must ensure that any soil and other materials that are removed from the site and identified as being contaminated are taken to a facility legally authorised to receive soil and materials of that kind.</li> <li>3 The consent holder must take all practicable measures to— <ol style="list-style-type: none"> <li>a) prevent the discharge of soil and stormwater from contaminated land to watercourses; and</li> <li>b) maintain the integrity of any structure designed to contain contaminated soil or other contaminated materials; and</li> <li>c) replace the soil to an erosion-resistant state at the completion of the relevant works.</li> </ol> </li> </ol> <p><b>Matters of control</b></p> <p>Contaminated land (human health)</p> <ol style="list-style-type: none"> <li>a) Potential adverse effects on human health from disturbance or use of contaminated soil.</li> <li>b) Measures to avoid, remedy, or mitigate those effects, including— <ol style="list-style-type: none"> <li>i. posed by contaminants; and</li> <li>ii. timing of remediation; and</li> <li>iii. standard of remediation on completion of works.</li> </ol> </li> </ol>	<p>A Detailed Site Investigation (DSI) and Contamination Site Management Plan (CSMP) has been prepared to address the requirements of Condition 17 and manage potential adverse effects on human health and the environment during and on completion of the stopbank construction. Condition 7(3) (e (ii)) requires that procedures for the management of hazards from the discharge of any contaminant are included in the Construction Environmental Management Plan (CEMP), which is required by Condition 10 of the OIC. Therefore, we recommend that the CSMP forms an appendix to the CEMP.</p>
18	<p><b>Works and structures in beds of rivers</b></p> <ol style="list-style-type: none"> <li>1 This clause and clauses 19 and 20 of this schedule apply to all construction works carried out in, or adjacent to, the bed of a river.</li> <li>2 The consent holder must ensure that construction works are, so far as practicable, carried out in accordance with— <ol style="list-style-type: none"> <li>a) an applicable ESCP; and</li> <li>b) the ecology principles; and</li> <li>c) the earthworks principles; and</li> <li>d) any guidance provided under clause 4(3)(b) of this schedule (see clause 5 of this schedule) relating to relevant cultural indicators.</li> </ol> </li> <li>3 Flood protection works that might affect fish passage in a river must, so far as practicable, be carried out outside peak times for migration and spawning of species of fish identified, in the ecological scoping survey conducted under clause 27 of this schedule, as being present in the river.</li> <li>4 Permanent works in or adjacent to the bed of a river that are completed as a part of the construction phase of the flood protection works (for example, sediment and debris removal, bank protection, and capacity increase) must— <ol style="list-style-type: none"> <li>a) be designed and installed in a way that is, so far as practicable, consistent with the ecology principles; and</li> <li>b) be designed by an engineer and an ecologist who are suitably qualified and experienced so as to provide for ongoing fish passage in the river; and</li> <li>c) manage stream loss, where threatened or at-risk species are present, in accordance with the effects management hierarchy; and</li> <li>d) provide for the maintenance of the river for flood management purposes.</li> </ol> </li> <li>5 The design of a permanent culvert in the bed of a river must— <ol style="list-style-type: none"> <li>a) allow for the relevant design flood flow event; and</li> <li>b) address the risks of non-performance (including blockage), taking into account the risk of the flow of soil or debris.</li> </ol> </li> <li>6 A permanent spillway or weir must ensure that— <ol style="list-style-type: none"> <li>a) a secondary flow path is available in the event of a blockage of the watercourse; and</li> <li>b) discharge from the secondary flow path does not exacerbate flooding of neighbouring or downstream properties.</li> </ol> </li> <li>7 All works and structures in, or adjacent to, rivers must, so far as practicable, incorporate energy dissipation measures and erosion and sediment control measures (for example, revegetation of worked sites) to minimise bed scouring and bank erosion in receiving environments</li> </ol>	<ul style="list-style-type: none"> <li>• There may be a requirement to cross the Okawa stream as part of earthworks haulage routes. This should be confirmed by the Contractor and details for temporary crossings should comply with the HBRC Working in Waterways Guidance, 2009.</li> </ul>
19	<p>Further requirements at watercourses</p> <ol style="list-style-type: none"> <li>1 This clause applies if clause 18 of this schedule applies.</li> </ol>	<ul style="list-style-type: none"> <li>• There may be a requirement to cross the Okawa stream as part of earthworks haulage routes. This should be confirmed by the Contractor and details for</li> </ul>

Number	Standardised conditions and proposed changes	Corresponding actions taken/design intent
	<p>2 Despite clause 18(4)(b) of this schedule, fish passage need not be provided and maintained on all permanent culverts if the Project Ecologist decides, after considering all relevant matters, that it is unnecessary.</p> <p>3 Instead, the consent holder must—</p> <ol style="list-style-type: none"> <li>give the consent authority appropriate data and reasons (supported by relevant design drawings) for not complying with clause 18(4)(b) of this schedule; and</li> <li>if culverts that do not provide fish passage are necessary, notify the Department of Conservation.</li> </ol> <p>4 For the purposes of clause 18 of this schedule, the consent holder must, at least 10 working days before starting permanent works within a watercourse, give to the consent authority—</p> <ol style="list-style-type: none"> <li>hard copies of the design drawings for permanent culverts (including fish passage), bridges, and permanent stream diversions; and</li> <li>a statement of how those designs comply with clause 18 of this schedule.</li> </ol> <p>5 All permanent works in the bed of a river must be carried out in accordance with the designs given to the consent authority under subclause (4).</p> <p>6 The consent holder must ensure that any machinery or equipment used in the activities authorised by the consent is not stored in or on the bed or banks of the watercourse.</p> <p>7 The consent holder must ensure all of the following:</p> <ol style="list-style-type: none"> <li>no machinery leaking fuel, lubricants, hydraulic fluids, or solvents is operated within or near a watercourse in circumstances where run-off might enter water;</li> <li>no vehicles, machinery, or equipment are refuelled within the bed of a watercourse or in any other location where spills might enter water;</li> <li>the storage of fuel or contaminants adjacent to a watercourse does not result in any fuel or contaminants entering water;</li> <li>other fuels and lubricants are not released into water;</li> <li>the Ministry for Primary Industries' requirements and clean dry protocols relating to didymo and freshwater pests are followed in relation to all equipment;</li> <li>machinery is operated in a way that minimises the transfer of organisms or pest plants from one catchment to another;</li> <li>the use of wet concrete is avoided in flowing water.</li> </ol> <p>8 The consent holder, on becoming aware that any contaminant has been discharged into a watercourse in a way that contravenes the conditions of the resource consent, must immediately—</p> <ol style="list-style-type: none"> <li>take all necessary steps to stop or contain the discharge; and</li> <li>notify— <ol style="list-style-type: none"> <li>the Manager Compliance; and</li> <li>the Department of Conservation, if there is imminent risk of the discharge adversely affecting any at-risk or threatened species; and</li> </ol> </li> <li>take all practicable steps to remedy or mitigate any ongoing adverse effects of the discharge on the environment.</li> </ol> <p>9 The consent holder must take the actions set out in subclause (10) in relation to construction material, demolition material, and any materials from repair and maintenance activities that are—</p> <ol style="list-style-type: none"> <li>authorised by the consent; and</li> <li>no longer required as part of the construction works.</li> </ol> <p>10 The consent holder must ensure that the materials are—</p> <ol style="list-style-type: none"> <li>removed on completion of the construction works; and</li> <li>reused, repurposed, or disposed of in an appropriate manner and in a place where they will not affect surface water levels and watercourses.</li> </ol> <p>11 The consent holder must comply with all notices and guidelines issued by Biosecurity New Zealand that relate to the ongoing prevention of the spread of freshwater pests.</p>	<p>temporary crossings should comply with the HBRC Working in Waterways Guidance, 2009.</p>
21	<p><b>Stormwater discharge</b></p> <p>1 The consent holder must, not later than 3 months after the completion of the construction works,—</p> <ol style="list-style-type: none"> <li>document the requirements for the effective operation and maintenance of all stormwater treatment devices (including sediment traps, if practicable); and</li> <li>submit the documents to the consent authority.</li> </ol> <p>2 The consent holder must design any new permanent culvert to ensure that any headwater ponding upstream in the relevant design event does not have any significant adverse effect in that area.</p> <p>3 The consent holder must ensure that stormwater discharge from construction works does not cause erosion or scouring of the bed or any bank of any downstream watercourse or receiving drain.</p> <p>4 The consent holder must ensure that the design of culverts and stormwater detention devices is, so far as practicable, in accordance with the HBRC Stormwater Management Guidelines.</p>	<ul style="list-style-type: none"> <li>(2) Culverts are sized to cater to a 100-year ARI event (due to the lack of a secondary flowpath and requirements of HDC Code of Practise). Accordingly, there are no adverse effects in a 100-year event, assuming the culvert can discharge. We note that in extreme flood events, the time of concentration of the Ohiti culverts are likely to be significantly shorter than that of the Okawa Stream catchment.</li> <li>(3) Erosion protection measures have been included on stormwater outlets, where they discharge into the Okawa, including rip rap aprons. These have been sized in accordance with HBRC Stormwater management guidelines. Further details will be clarified at detailed design.</li> <li>(4) Culverts have been designed to HBRC Stormwater Management Guidelines</li> </ul>

## **Appendix C      Risk Register**

---

Ref ID #	Threat/ Opportunity	Risk Name	Risk Description	Risk Category (edit on Reference Tab)	Existing Control(s) (if any)	Risk Assessment (with Existing Controls)			Possible treatment/mitigation	Risk Assessment (after treatment)			Risk Owner
						Likelihood	Consequence	Risk Rating		Likelihood	Consequence	Risk Rating	
1	Threat	Uncertainty with flood level estimates	Uncertainty leads to overtopping of stopbanks in flood events.	Safety	HBRC to provide clear expectations on flood design cases and levels of performance. T+T to provide clear limitations of flood modelling data.	Possible	Major	Moderate	Contingency in design aligns with uncertainty of flood models.	Unlikely	Major	Moderate	HBRC
2	Threat	Insufficient borrow material	Insufficient borrow material to complete contract works, leads to delays and associated costs with contractor stand down.	Construction	Geotechnical investigations completed. Contractor to review earthworks volumes to ensure proposed methodology manages materials appropriately.	Unlikely	Major	Moderate	Contractor to monitor volumes throughout the construct and update project team on material supply.	Unlikely	Major	Moderate	HBRC/Contractor
3	Threat	Unsuitable material more than estimated	Unsuitable material is greater than estimated leading to additional borrow material being required.	Construction	Test pits and geotechnical investigations through the stopbank have been undertaken	Unlikely	Moderate	Moderate	Review during construction. HBRC to allow contingency in contract for remedial works.	Unlikely	Minor	Low	HBRC
4	Threat	Poor quality material from borrow area.	Material extracted from borrow area does not comply with project specification.	Construction	Geotechnical investigations undertaken.	Possible	Moderate	Moderate	Contingent allowance to import material or blend to meet specification requirements.	Unlikely	Moderate	Moderate	HBRC/Designer
5	Threat	Weather	Poor weather leading to contract delays and material too wet to compact and achieve specification.	Environmental	Programme to make allowance for wet weather.	Likely	Moderate	Moderate	Cover works areas to minimise moisture ingress and saturation of embankments. Erosion and sediment control to minimise ponding of water and additional measures to be included before significant wet weather periods.	Likely	Moderate	Moderate	HBRC/Contractor
6	Threat	Flooding	Flooding leading to disruption of site works and potential scour of worksites/open faces.	Environmental	Specification requirements to include emergency procedures for flooding.	Possible	Major	Moderate	Contractor to manage site and have preparation and layout down areas above stopbank. Forecast to be monitored and a working procedure if flooding arises to be developed and managed on site. Minimise open faces to prevent scour or protect works areas prior to floodwaters arise. Erosion and sediment control plan to consider this risk.	Possible	Minor	Moderate	Contractor and HBRC
7	Threat	Scour and erosion	Heavy rainfall leading to scour of existing open faces during works	Construction	Minimise open faces and plans works with non-erosive material where possible.	Likely	Minor	Moderate	Contractor to manage slope and grade away from working area. Contractor to stabilise areas where necessary to protect erosion.	Possible	Moderate	Moderate	Contractor
8	Threat	Dust	Excessive dust caused by project works, leading to complaints and enforcement action.	Environmental	Works schedule to be undertaken in stages to minimise open faces.	Possible	Moderate	Moderate	Contractor to prepare ESCP and maintain operation effectiveness of devices. Water usage from river as dust suppression.	Unlikely	Minor	Low	Contractor
9	Threat	Erosion controls	Erosion and sediment control failures, leading to environmental discharge and enforcement.	Environmental	ESCP requirements to be defined by HBRC as part of tender documents.	Possible	Major	Moderate	Contractor to prepare ESCP and maintain operation effectiveness of devices.	Unlikely	Minor	Low	Contractor
10	Threat	Contamination	Contaminated soils identified during contract works. Leads to additional costs for disposal, delays and additional management on site.	Environmental	Contaminated soil investigations undertaken.	Unlikely	Major	Moderate	Include contingency for unlikely event of contamination.	Unlikely	Minor	Low	HBRC
11	Threat	Programme delays and coordination with stakeholders	Programme delays and associated costs due to delays in coordinating with neighbouring sites.	Stakeholder	HBRC have liaised with stakeholders.	Possible	Moderate	Moderate	Coordinate works around stakeholder key working windows.	Unlikely	Minor	Low	HBRC
12	Threat	Procurement of materials	Delays to project due to procurement constraints from suppliers.	Stakeholder	Materials are relatively limited (i.e. culverts)	Possible	Minor	Moderate	Programme works around long lead time items	Unlikely	Minor	Low	Contractor
13	Threat	Earthworks quality assurance and control	QA/QC testing delayed or not provided to designer with sufficient notice to review. Reworks to remediate areas identified.	Engineering/Design	QA requirements in specification clearly laid out.	Unlikely	Minor	Low	Contractor to provide quality management plan to ensure clear QA/QC testing requirements and hold periods.	Rare	Minor	Low	Contractor
14	Threat	Stopbank preparation and backfill material placement	Insufficient fill placement preparation, or poor in-situ soils, and improper compaction of stopbank fill leading to deficiencies.	Engineering/Design	QA requirements in specification clearly laid out.	Possible	Major	Moderate	QA/QC during construction. Contractor to address in quality management plan.	Unlikely	Minor	Low	Contractor
15	Threat	Culvert bedding and backfill	Insufficient compaction on bedding surrounding, leading to deficiencies	Engineering/Design	QA requirements in specification clearly laid out.	Possible	Major	Moderate	QA/QC during construction. Contractor to address in quality management plan.	Unlikely	Minor	Low	Contractor
16	Threat	Consenting requirements	Works delayed due to requirements for consents or permits (for example water abstraction or fill import).	Consenting	HBRC to manage permit requirements and clearly lay out in the tender documents.	Possible	Minor	Moderate	HBRC to confirm consent requirements ahead of works commencement and manage permit requirements to assist contractor. Contractor to comply with consent requirements and notifications.	Unlikely	Minor	Low	HBRC/Contractor
17	Threat	Working near waterways	Works not following requirements for working near waterways, impacts on environment.	Construction	HBRC to manage permit requirements and clearly lay out in the tender documents.	Possible	Minor	Moderate	Contractor to have safe work method statements in place and followed appropriately.	Unlikely	Minor	Low	HBRC/Contractor
18	Threat	Working around slopes and water - hazards to workers	Slope and water hazards to workers.	Construction	HBRC to clearly lay out H&S requirements in the tender documents.	Possible	Major	Moderate	Contractor to have safe work method statements in place and followed appropriately.	Unlikely	Minor	Low	Contractor
19	Threat	Constructor expertise and/or experience.	Constructor does not undertake works in an efficient manner to the expected standard.	Construction	HBRC to provide clear expectations and requirements in the tender documents.	Possible	Moderate	Moderate	Contractor to provide clear work method statements and QA/QC processes.	Unlikely	Minor	Low	HBRC/Contractor
20	Threat	Traffic management	Vehicle access around site, driving on slopes and interface with public roadways and driveways. Traffic management and public access during the raising of Ohiti and Taihape roads.	Construction	HBRC to clearly lay out H&S and traffic management requirements in the tender documents.	Possible	Minor	Moderate	Contractor to have safe work method statements and traffic management plans in place and followed appropriately.	Unlikely	Minor	Low	Contractor

